

1] LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Reno</u>		<u>NW 1/4 NW 1/4 NE 1/4</u>	<u>26</u>	T <u>24</u> S	R <u>5</u> E <u>(W)</u>
Distance and direction from nearest town or city street address of well if located within city? <u>1 1/2 mi E of Yoder</u>					
2] WATER WELL OWNER:					
RR#, St. Address, Box # : <u>Harry A Bontroyer</u>					
City, State, ZIP Code : <u>Rt 2, Box 274 A Haven, KS 67543</u>					
Board of Agriculture, Division of Water Resources Application Number:					
3] LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4] DEPTH OF COMPLETED WELL: <u>69</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL ... <u>30</u> ... ft. below land surface measured on mo/day/yr <u>11-29-90</u>			
		Pump test data: Well water was ... <u>32</u> ... ft. after ... <u>1</u> ... hours pumping ... <u>25</u> ... gpm			
		Est. Yield gpm: Well water was ft. after hours pumping gpm			
		Bore Hole Diameter ... <u>9</u> ... in. to ... <u>72</u> ... ft., and ... in. to ... ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering <u>(2) Other (Specify below)</u> 2 Irrigation 7 Lawn and garden only 10 Monitoring well <u>5% CK</u>			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No... <u>X</u> ; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes <u>X</u> No			
5] TYPE OF BLANK CASING USED:					
1 Steel		3 RMP (SR)		5 Wrought iron	
<u>(2) PVC</u>		4 ABS		6 Asbestos-Cement	
				7 Fiberglass	
Blank casing diameter ... <u>6</u> ... in. to ... <u>59</u> ... ft., Dia				8 Concrete tile	
Casing height above land surface ... <u>12</u> ... in., weight ... <u>3.25</u> ... lbs./ft.				9 Other (specify below)	
TYPE OF SCREEN OR PERFORATION MATERIAL:				CASING JOINTS: Glued <u>X</u> Clamped	
1 Steel		3 Stainless steel		Welded	
2 Brass		4 Galvanized steel		Threaded	
SCREEN OR PERFORATION OPENINGS ARE:		5 Fiberglass			
1 Continuous slot		6 Concrete tile		10 Asbestos-cement	
2 Louvered shutter		7 Torch cut		11 Other (specify)	
3 Mill slot		8 RMP (SR)		12 None used (open hole)	
4 Key punched		9 ABS			
SCREEN-PERFORATED INTERVALS:		10 Saw cut		11 None (open hole)	
From ... <u>59</u> ... ft. to ... <u>69</u> ... ft.		9 Drilled holes			
GRAVEL PACK INTERVALS:		10 Other (specify)			
From ... <u>20</u> ... ft. to ... <u>45</u> ... ft.					
From ... <u>50</u> ... ft. to ... <u>72</u> ... ft.					
6] GROUT MATERIAL:					
1 Neat cement		2 Cement grout		3 Bentonite	
Grout Intervals: From ... <u>0</u> ... ft. to ... <u>20</u> ... ft.		4 Other		From ... <u>45</u> ... ft. to ... <u>50</u> ... ft.	
What is the nearest source of possible contamination:					
1 Septic tank		4 Lateral lines		7 Pit privy	
2 Sewer lines		5 Cess pool		8 Sewage lagoon	
3 Watertight sewer lines		6 Seepage pit		9 Feedyard	
Direction from well? <u>S-SE</u>				How many feet? <u>625</u>	
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
<u>0</u>	<u>55</u>	<u>Br clay</u>			
<u>55</u>	<u>60</u>	<u>C Sand</u>			
<u>60</u>	<u>69</u>	<u>Sand + Med Gravel</u>			
<u>69</u>	<u>72</u>	<u>Shale</u>			
7] CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>(1)</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) ... <u>11-29-90</u> ... and this record is true to the best of my knowledge and belief. Kansas					
Water Well Contractor's License No. ... <u>447</u> ... This Water Well Record was completed on (mo/day/yr) ... <u>12-4-90</u> ...					
under the business name of <u>Miller Drilling</u> by (signature) <u>G Miller</u>					

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-7320. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.