

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Reno</u>	<u>NE 1/4 NE 1/4 SE 1/4</u>	<u>7</u>	<u>T 24 S</u>	<u>R 6 EW</u>

Distance and direction from nearest town or city street address of well if located within city?

4 mi E, 1/2 N of Partridge

2 WATER WELL OWNER:	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	Application Number:
City, State, ZIP Code :	

Willis Miller5817 W Longview RdHatch, KS 67501

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: <u>51</u> ft. ELEVATION:
	Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL <u>23</u> ft. below land surface measured on mo/day/yr <u>10-24-95</u>
	Pump test data: Well water was <u>43</u> ft. after <u>1</u> hours pumping <u>20</u> gpm
	Est. Yield gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter <u>8</u> in. to <u>54</u> ft., and in. to ft.
WELL WATER TO BE USED AS:	
☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
☐ 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well	
Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes <u>X</u> No	

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued <u>X</u> Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
<u>2</u> PVC	4 ABS	7 Fiberglass	Welded
Blank casing diameter <u>5</u> in. to <u>41</u> ft., Dia			Threaded
Casing height above land surface <u>12</u> in., weight <u>2.29</u> lbs./ft. Wall thickness or gauge No. <u>160</u>			
TYPE OF SCREEN OR PERFORATION MATERIAL:			
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:			
1 Continuous slot	3 Mill slot	5 Gauzed wrapped	<u>8</u> Saw cut
2 Louvered shutter	4 Key punched	6 Wire wrapped	9 Drilled holes
SCREEN-PERFORATED INTERVALS: From <u>41</u> ft. to <u>51</u> ft., From ft. to ft.			
GRAVEL PACK INTERVALS: From ft. to ft., From ft. to ft.			

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals: From <u>3</u> ft. to <u>23</u> ft., From ft. to ft., From ft. to ft.				
What is the nearest source of possible contamination:				
<u>1</u> Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
Direction from well? <u>S-SW</u> How many feet? <u>100</u>				

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
<u>0</u>	<u>7</u>	<u>Br clay</u>			
<u>7</u>	<u>21</u>	<u>F-C sand</u>			
<u>21</u>	<u>29</u>	<u>F sand</u>			
<u>29</u>	<u>51</u>	<u>F-C sand</u>			
<u>51</u>	<u>54</u>	<u>Shale</u>			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>1</u> constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>10-24-95</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>447</u> This Water Well Record was completed on (mo/day/yr) <u>11-7-95</u> under the business name of <u>Miller Drilling</u> by (signature) <u>E. Miller</u>
--