


USE TYPEWRITER OR BALL  
POINT PEN-PRESS FIRMLY,  
PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and  
Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well:	County <b>Reno</b>	Fraction <b>NW 1/4 NE 1/4 NW 1/4</b>	Section number <b>11</b>	Township number <b>T 24 S R 6</b>	Range number <b>6</b>
2. Distance and direction from nearest town or city: <b>2 m. South &amp; 1 West of South Hutchinson</b>			3. Owner of well: <b>City of South Hutchinson Hutchinson</b> R.R. or street: <b>Kansas 67501</b> City, state, zip code:		
4. Locate with "X" in section below: 			Sketch map: <b>Well No. 1</b> <b>Test Hole 1-78</b>		
5. Type and color of material			From	To	6. Bore hole dia. <b>30</b> in. Completion date Well depth <b>132</b> ft. <b>10/31/78</b>
<b>Soil</b>			<b>0</b>	<b>3</b>	7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary
<b>Clay</b>			<b>3</b>	<b>15</b>	8. Use: <input type="checkbox"/> Domestic <input checked="" type="checkbox"/> Public supply <input type="checkbox"/> Industry <input type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other
<b>Fine sand</b>			<b>15</b>	<b>26</b>	9. Casing: Material <b>St. Steel</b> Weight: Above <input type="checkbox"/> Below <input type="checkbox"/> Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>42</b> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <b>62.58</b> lbs./ft. Dia. <b>16</b> in. to <b>110</b> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth Gauge No. <b>.375"</b>
<b>Tan clay</b>			<b>26</b>	<b>42</b>	10. Screen: Manufacturer's name <b>Layne &amp; Bowler</b> Type <b>Stainless</b> Dia. <b>16"</b> Slot/gauge <b>.105</b> Length <b>25'</b> Set between <b>107</b> ft. and <b>132</b> ft. ft. and <input type="checkbox"/> ft. Gravel pack? <b>yes</b> Size range of material <b>1/4" x 1/8"</b>
<b>Med. to coarse sand</b>			<b>42</b>	<b>56</b>	11. Static water level: <input type="checkbox"/> mo./day/yr. <b>22</b> ft. below land surface Date <b>10/31/78</b>
<b>Tan clay</b>			<b>56</b>	<b>71</b>	12. Pumping level below land surfaces: <b>53</b> ft. after <b>8</b> hrs. pumping <b>900</b> g.p.m. ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield <b>1500</b> g.p.m.
<b>Med. to coarse sand</b>			<b>71</b>	<b>99</b>	13. Water sample submitted: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Date <input type="checkbox"/>
<b>Tan clay</b>			<b>99</b>	<b>107</b>	14. Well head completion: <input type="checkbox"/> Pitless adapter <b>42</b> Inches above grade
<b>Med. to coarse sand</b>			<b>107</b>	<b>132</b>	15. Well grouted? <b>yes</b> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From <b>0</b> ft. to <b>20</b> ft.
<b>Tan clay</b>			<b>132</b>		16. Nearest source of possible contamination: ft. <b>600</b> Direction <b>East</b> Type <b>Farm</b> Well disinfected upon completion? <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No
					17. Pump: Manufacturer's name <b>Layne &amp; Bowler</b> Not installed Model number <b>11 B</b> HP <b>60</b> Volts <b>460</b> Length of drop pipe <b>120</b> ft. capacity <b>700</b> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other
18. Elevation:			19. Remarks:		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley			20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <b>Layne Western Co. 102</b> Business name License No. Address <b>Wichita, Kansas</b> Signed <b>W. H. Hoke</b> Date <b>11/4/78</b> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5