

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

47,374

1 LOCATION OF WATER WELL: County: Reno		Fraction SW ¼ SW ¼ NE ¼ SE ¼		Section Number 29		Township No. T 24 S		Range Number R 7 ☐ E ☒ W																																																																			
2 WATER WELL OWNER: Glenn Depew RR#, Street Address, Box #: 407 North Dean Road City, State, ZIP Code : Hutchinson, Kansas 67501				Global Positioning System (GPS) information: Latitude: .37.93038..... (in decimal degrees) Longitude: 098.10973..... (in decimal degrees) Elevation: 1593..... Datum: ☐ WGS 84, ☐ NAD 83, ☒ NAD 27 Collection Method: ☒ GPS unit (Make/Model: Garmin csx.....) ☐ Digital Map/Photo, ☒ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																							
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="border-collapse: collapse; text-align: center;"> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td></tr> </table> E S 1 mile											4 DEPTH OF COMPLETED WELL 61 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 30..... ft. below land surface measured on mo/day/yr. 11-5-10..... Pump test data: Well water was..... ft. after..... hours pumping..... gpm EST. YIELD..... gpm. Well water was..... ft. after..... hours pumping..... gpm Bore Hole Diameter in. to ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No																																																																
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter .16..... in. to .41..... ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface .20..... in., Weight SCH.40..... lbs./ft., Wall thickness or gauge No. 500..... TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From .41..... ft. to .61..... ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From .61..... ft. to .20..... ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																											
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☒ Other dirt Grout Intervals: From .20..... ft. to .2..... ft., From 2..... ft. to 0..... ft., From ft. to ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well none..... Direction from well Distance from well																																																																											
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:40%;">LITHOLOGIC LOG</th> <th style="width:10%;">FROM</th> <th style="width:10%;">TO</th> <th style="width:20%;">LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>2</td> <td>Sandy top soil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>2</td> <td>12</td> <td>Tan clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>12</td> <td>20</td> <td>Whiteish tan clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>20</td> <td>60</td> <td>Med. to fine sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>60</td> <td>61</td> <td>Red shale</td> <td></td> <td></td> <td></td> </tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> <tr><td> </td><td> </td><td> </td><td> </td><td> </td><td> </td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	2	Sandy top soil				2	12	Tan clay				12	20	Whiteish tan clay				20	60	Med. to fine sand				60	61	Red shale																																	
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																						
0	2	Sandy top soil																																																																									
2	12	Tan clay																																																																									
12	20	Whiteish tan clay																																																																									
20	60	Med. to fine sand																																																																									
60	61	Red shale																																																																									
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 11-5-10..... and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134..... This Water Well Record was completed on (mo/day/year) 11-12-10..... under the business name of Rosencrantz Bemis Ent. by (signature) <i>Rosencrantz Bemis Ent.</i>																																																																											
INSTRUCTIONS: Use typewriter or ball point pen. <u>PLEASE PRESS FIRMLY and PRINT</u> clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																											