


1 LOCATION OF WATER WELL: County: Sedgwick	Fraction NE 1/4 NE 1/4 NW 1/4	Section Number 7	Township Number T 25 S	Range Number R 1 E
--	---	----------------------------	----------------------------------	------------------------------

Distance and direction from nearest town or city street address of well if located within city?

1 Mile North & 2 miles East of Bentley, Ks.

2 WATER WELL OWNER: RR#, St. Address, Box # : City, State, ZIP Code	City Water Department City Hall - 455 N. Main St. Wichita, Kansas 67201	Well No. M35 Board of Agriculture, Division of Water Resources Application Number: 388
---	--	--

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 	4 DEPTH OF COMPLETED WELL 132'6" ft. ELEVATION: 30'7" ft.
	Depth(s) Groundwater Encountered 1. 30'7" ft. 2. 30'7" ft. 3. 30'7" ft.
	WELL'S STATIC WATER LEVEL 30'7" ft. below land surface measured on mo/day/yr 10/1/81
	Pump test data: Well water was 56 ft. after 8 hours pumping 1250 gpm
Est. Yield 30 gpm: Well water was 56 ft. after 8 hours pumping 1250 gpm	
Bore Hole Diameter 30 in. to 64 ft., and 42 in. to 134 ft.	
WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well	
Was a chemical/bacteriological sample submitted to Department? Yes X No X ; If yes, mo/day/yr sample was submitted	
Water Well Disinfected? Yes X No X	

5 TYPE OF BLANK CASING USED: 1 Steel 2 PVC Blank casing diameter 18 in. to 64 ft., Dia 18 in. to 64 ft., Dia 18 in. to 64 ft.	3 RMP (SR) 4 ABS Blank casing diameter 18 in. to 64 ft., Dia 18 in. to 64 ft., Dia 18 in. to 64 ft.	5 Wrought iron 6 Asbestos-Cement 7 Fiberglass Blank casing diameter 18 in. to 64 ft., Dia 18 in. to 64 ft., Dia 18 in. to 64 ft.	8 Concrete tile 9 Other (specify below) Blank casing diameter 18 in. to 64 ft., Dia 18 in. to 64 ft., Dia 18 in. to 64 ft.	CASING JOINTS: Glued X Clamped X Welded X Threaded X
TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 7 PVC 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 8 RMP (SR) 11 Other (specify) 1375 12 None used (open hole)				
SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify)				
SCREEN-PERFORATED INTERVALS: From 64 ft. to 74 ft., From 107 ft. to 134 ft.				
GRAVEL PACK INTERVALS: From 20 ft. to 134 ft., From 107 ft. to 134 ft.				

6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other	Grout Intervals: From 0 ft. to 20 ft., From 107 ft. to 134 ft.
What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage	Direction from well? South How many feet? 60

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	4	Sandy soil	133	134	Tan clay
4	15	Fine to med. sand			
15	25	Med. to co. sand & gravel			
25	30	Clay			
30	80	Med. to co. sand & gravel			
80	82	Fine to coarse sand			
82	90	Clay w/sand & gravel			
90	91	Fine to coarse sand			
91	98	Green clay			
98	106	Tan clay			
106	108	Med. sand, clay lenses			
108	122	Green clay/traces of sand			
122	125	Co. sand w/green-tan clay			
125	127	Co. sand/some clay			
127	133	Fine-med. sand			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 9/14/81 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 102 This Water Well Record was completed on (mo/day/yr) 10/1/81 under the business name of Layne Western Co., Inc. by (signature) <i>[Signature]</i>

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.