

LOCATION OF WATER WELL		Fraction	Section Number	Township Number	Range Number
County: <u>SEDGWICK</u> NW 1/4 NE 1/4 NE 1/4			<u>1</u>	T <u>25</u> S	R <u>1</u> EW
Distance and direction from nearest town or city? <u>2 3/4 E of SEDGWICK</u>			Street address of well if located within city?		

WATER WELL OWNER: <u>RONALD J. BOGUNOVICH</u>		Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: <u>RR #1</u>		Application Number:
City, State, ZIP Code: <u>SEDGWICK, KS</u>		

DEPTH OF COMPLETED WELL: <u>68</u> ft.		Bore Hole Diameter: <u>11</u> in. to <u>68</u> ft., and in. to ft.
Well Water to be used as:		
1 Domestic <u>(circled)</u>	3 Feedlot	5 Public water supply
2 Irrigation	4 Industrial	6 Oil field water supply
		7 Lawn and garden only
		8 Air conditioning
		9 Dewatering
		10 Observation well
11 Injection well		
12 Other (Specify below)		
Well's static water level: <u>26</u> ft. below land surface measured on <u>1</u> month <u>6</u> day <u>81</u> year		
Pump Test Data: Well water was <u>1/64</u> ft. after <u>1 1/2</u> hours pumping. <u>12</u> gpm		
Est. Yield <u>12/14</u> gpm: Well water was ft. after hours pumping gpm		

TYPE OF BLANK CASING USED:		5 Wrought iron	8 Concrete tile	Casing Joints: Glued <u>X</u> Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)	Welded
<u>2 PVC</u> <u>(circled)</u>	4 ABS	7 Fiberglass		Threaded
Blank casing dia: <u>5</u> in. to <u>45</u> ft., Dia in. to ft., Dia in. to ft.				
Casing height above land surface: <u>24</u> in., weight lbs./ft. Wall thickness or gauge No.				

TYPE OF SCREEN OR PERFORATION MATERIAL:		<u>7 PVC</u> <u>(circled)</u>	10 Asbestos-cement
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
Screen or Perforation Openings Are:		5 Gauzed wrapped	<u>8 Saw cut</u> <u>factory</u> <u>(circled)</u>
1 Continuous slot	3 Mill slot	6 Wire wrapped	1020 slot
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
Screen-Perforation Dia: <u>5</u> in. to <u>65</u> ft., Dia in. to ft., Dia in. to ft.			
Screen-Perforated Intervals: From <u>45</u> ft. to <u>65</u> ft., From ft. to ft., From ft. to ft.			
Gravel Pack Intervals: From <u>10</u> ft. to <u>68</u> ft., From ft. to ft., From ft. to ft.			

GROUT MATERIAL:		1 Neat cement	2 Cement grout	<u>3 Bentonite</u> <u>(circled)</u>	4 Other
Grouted Intervals: From <u>0</u> ft. to <u>10</u> ft., From ft. to ft., From ft. to ft.					
What is the nearest source of possible contamination:					
1 Septic tank	4 Cess pool	7 Sewage lagoon	10 Fuel storage	14 Abandoned water well	
<u>2 Sewer lines</u> <u>(circled)</u>	5 Seepage pit	8 Feed yard	11 Fertilizer storage	15 Oil well/Gas well	
3 Lateral lines	6 Pit privy	9 Livestock pens	12 Insecticide storage	16 Other (specify below)	
Direction from well: <u>UNKNOWN</u> How many feet: <u>UNKNOWN</u> Water Well Disinfected? Yes <u>X</u> No					
Was a chemical/bacteriological sample submitted to Department? Yes No If yes, date sample was submitted month day year: Pump Installed? Yes No					
If Yes: Pump Manufacturer's name Model No. HP Volts					
Depth of Pump Intake ft. Pumps Capacity rated at gal./min.					
Type of pump: 1 Submersible 2 Turbine 3 Jet <u>(circled)</u> 4 Centrifugal 5 Reciprocating 6 Other					

CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was <u>(1) constructed</u> <u>(circled)</u> (2) reconstructed, or (3) plugged under my jurisdiction and was completed on month <u>12</u> day <u>81</u> year <u>1975</u>					
and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>175</u>					
This Water Well Record was completed on month <u>2</u> day <u>81</u> year under the business name of <u>PAUL'S INC.</u> by (signature) <u>Paul Bunthout</u>					

	LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
		0	5	Loam			
		5	10	red br. clay			
		10	15	red sandy br. clay			
		15	42	light br. clay			
		42	45	grey clay			
		45	50	light sandy grey clay to			
		50	62	light brown clay with thin sand seams			
	62	65	coarse sand				
	65	68	Shale - dark grey				

ELEVATION:	* NEW House to be built at later date			
Depth(s) Groundwater Encountered	1 ft.	2 ft.	3 ft.	4 ft.

(Use a second sheet if needed)

INSTRUCTIONS: Use typewriter or ball point pen, please press firmly and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Water Well Contractors, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.