


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Sedgwick	Fraction Center of West 1/2 SW 1/4	Section number 4	Township number T 25 S R 1	Range number EW
2. Distance and direction from nearest town or city: 1 mile South of Sedgwick, KS Street address of well location if in city:		3. Owner of well: Kenneth McGinn R.R. or street: Route 2 City, state, zip code: Sedgwick, KS 67135			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile 		Sketch map: 6. Bore hole dia. 24 in. Completion date 5-15-79 Well depth 127 ft. Pump Set 5-31-79 7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary 8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 77 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga. 10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot/gauze 1/8" Length 50' Set between 77 ft. and 127 ft. ☐ ft. and ☐ ft. Gravel pack? Yes Size range of material 3/8-200 11. Static water level: ☐ mo./day/yr. 17 ft. below land surface Date 5-15-79 12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m. 13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐ 14. Well head completion: ☐ Pitless adapter ☐ 12 Inches above grade 15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft. 16. Nearest source of possible contamination: FIELD ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No 17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Co. Model number 12MB-4 HP 80 Volts --- Length of drop pipe 80 ft. capacity 700 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name Great Bend, KS 67530 License No. Address 6-7-79 Signed [Signature] Date 6-7-79 Authorized representative			
5. Type and color of material	From	To			
Top soil & sand	0	7			
Sand & gravel	7	19			
Blue clay	19	25			
Sand & gravel	25	68			
Sand & gravel & thin clay streaks	68	79			
Sand & gravel	79	96			
Brown clay	96	101			
Sand & gravel	101	127			
(Use a second sheet if needed)					
18. Elevation:	19. Remarks:				
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley					

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5