


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Sedgwick</u>	Fraction <u>C S 1/2</u> 1/4 <u>SW</u> 1/4	Section number <u>5</u>	Township number <u>T 25 S R 1</u>	Range number <u>1</u>
2. Distance and direction from nearest town or city: Street address of well location if in city: <u>1 W. & So. Sedgwick</u>			3. Owner of well: <u>Jon Broadhurst</u> R.R. or street: <u>Sedgwick, Kansas.</u> City, state, zip code:			
4. Locate with "X" in section below:		Sketch map: <u>(open field)</u> <u>center of</u> <u>E 1/2 of SW 1/4 &</u> <u>W 1/2 of SE 1/4</u>		6. Bore hole dia. <u>30</u> in. Completion date <u>3/21/77</u> Well depth <u>100</u> ft.		
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material		From To		8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Topsoil</u>		<u>0 1</u>		9. Casing: Material <u>C-Asb</u> Height: Above or below Threaded ☐ Welded ☐ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. <u>4 1/2</u> in. to <u>61</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>3/4"</u>		
<u>Sand</u>		<u>1 20</u>		10. Screen: Manufacturer's name <u>Johnson</u> Type <u>Cement-Asb</u> Dia. <u>16"</u> Slot/gauze <u>44</u> Length <u>39'</u> Set between <u>61</u> ft. and <u>100</u> ft. ☐ ft. and ☐ ft.		
<u>Clay</u>		<u>20 30</u>		Gravel pack? ☒ Size range of material <u>3/8</u>		
<u>Good Gravel</u>		<u>30 65</u>		11. Static water level: ☐ mo./day/yr. <u>18</u> ft. below land surface Date <u>3/19/77</u>		
<u>Clay</u>		<u>65 74</u>		12. Pumping level below land surfaces: <u>23</u> ft. after <u>1</u> hrs. pumping <u>700</u> g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield <u>800</u> g.p.m.		
<u>Med. Gravel</u>		<u>74 80</u>		13. Water sample submitted: ☐ Yes ☒ No Date ☐		
<u>Clay</u>		<u>80 85</u>		14. Well head completion: <u>12</u> inches above grade ☐ Pitless adapter		
<u>med fine sand</u>		<u>85 88</u>		15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
<u>Clay</u>		<u>88 90</u>		16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No		
<u>m. Sand</u>		<u>90 95</u>		17. Pump: ☐ Not installed Manufacturer's name <u>Peerless</u> Model number <u>7038</u> HP <u>40</u> Volts ☐ Length of drop pipe <u>70</u> ft. capacity <u>750</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Weninger Irrigation</u> <u>238</u> Business name License No. Address <u>Maize</u> Signed <u>K. Weninger</u> Date <u>3/22/77</u> Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5