


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction SW 1/4 SE 1/4 NE 1/4	Section number 5	Township number T 25 S R 1	Range number 1	EW
2. Distance and direction from nearest town or city: Street address of well location if in city:		1 mi 1/2 S. Sedgwick		3. Owner of well: Fred Matzek R.R. or street: R.R. 2 City, state, zip code: Sedgwick, Kansas			
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. 30 in. Completion date 7/23/96 Well depth 100 ft.			
5. Type and color of material		From	To	7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary			
0 - 1 ft. Topsoil		0	1	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other			
Gray clay w/sand		1	10	9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 16 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/4			
Fine gray sand		10	30	10. Screen: Manufacturer's name Johnson Type Cement-Asb Dia. 16 Slot/gauze 44 Length Set between 61 ft. and 100 ft. ft. and ☐ ft.			
Medium fine sand		30	45	Gravel pack? Yes Size range of material 3/8			
Clay		45	60	11. Static water level: ☐ mo./day/yr. 25 ft. below land surface Date ☐			
Fair to Good Gravel		60	100	12. Pumping level below land surfaces: 35 ft. after 2 hrs. pumping 950 g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1000 g.p.m.			
				13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐			
				14. Well head completion: ☐ Pitless adapter 18 Inches above grade			
				15. Well grouted? Yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.			
				16. Nearest source of possible contamination: ft. 1000 Direction E Type Domestic Well disinfected upon completion? ☐ Yes ☒ No			
				17. Pump: Manufacturer's name Peerless Not installed Model number 6263 HP ☐ Volts ☐ Length of drop pipe 80 ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other			
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Drilling 238 Business name Maize, Kans 67101 License No. Address R. Weninger Date 8/23/96 Signed R. Weninger Authorized representative			

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5