

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 SW 1/4 SW 1/4	Section number 16	Township number T 25 S R 1 E W	Range number 1																														
2. Distance and direction from nearest town or city: Street address of well location if in city: 3 S, 3/4 W Sedgwick				3. Owner of well: Arlo Norstead R.R. or street: City, state, zip code: Sedgwick, Kansas																																
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 30 in. Completion date 7/13/78 Well depth 93 ft.																																
		open field		7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary																																
				8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																
5. Type and color of material				From	To	9. Casing: Material C-Asb Height: Above or below Threaded ☐ Welded ☐ Surface 18 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 16 in. to 93 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 3/4"																														
<table border="1" style="width:100%; border-collapse: collapse;"> <tr><td>Topsoil</td><td>0</td><td>1</td></tr> <tr><td>Fine Sand</td><td>1</td><td>15</td></tr> <tr><td>Clay</td><td>15</td><td>23</td></tr> <tr><td>Sand (Small)</td><td>23</td><td>40</td></tr> <tr><td>Clay</td><td>40</td><td>46</td></tr> <tr><td>Sand (Med)</td><td>46</td><td>66</td></tr> <tr><td>Clay</td><td>66</td><td>70</td></tr> <tr><td>Sand (Med)</td><td>70</td><td>85</td></tr> <tr><td>Clay</td><td>85</td><td>89</td></tr> <tr><td>Good Gravel</td><td>89</td><td>93</td></tr> </table>				Topsoil	0	1	Fine Sand	1	15	Clay	15	23	Sand (Small)	23	40	Clay	40	46	Sand (Med)	46	66	Clay	66	70	Sand (Med)	70	85	Clay	85	89	Good Gravel	89	93	10. Screen: Manufacturer's name Johnson Type Cement-Asb Dia. 16" Slot/gauze 44" Length 39' Set between 54 ft. and 93 ft. ft. and ft. Gravel pack? ☒ Size range of material 3/8		
				Topsoil	0	1																														
				Fine Sand	1	15																														
				Clay	15	23																														
				Sand (Small)	23	40																														
				Clay	40	46																														
				Sand (Med)	46	66																														
				Clay	66	70																														
				Sand (Med)	70	85																														
				Clay	85	89																														
Good Gravel	89	93																																		
11. Static water level: 18 ft. below land surface Date 7/13/78 mo./day/yr.																																				
12. Pumping level below land surfaces: 34 ft. after 2 hrs. pumping 900 g.p.m. 34 ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield 1100 g.p.m.																																				
13. Water sample submitted: ☐ Yes ☒ No Date ☐ mo./day/yr.																																				
14. Well head completion: ☐ Pitless adapter 15 Inches above grade																																				
15. Well grouted? ☒ With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 0 ft. to 10 ft.																																				
16. Nearest source of possible contamination: None ft. Direction Type Well disinfected upon completion? ☐ Yes ☒ No																																				
17. Pump: ☐ Not installed Manufacturer's name Peerless Model number 8451 HP 25 Volts Length of drop pipe 60' ft. capacity 1000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																				
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Irrigation Business name Maize, Ks. License No. Address Maize, Ks. Signed K. Weninger Date 8/10/78 Authorized representative																																

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5