


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

T R EW sec 1/4 1/4 1/4 No.

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:	County Sedgwick	Township name Valley	Fraction SW¹/₄ NW¹/₄ NE¹/₄	Section number 20	Town number 25	Range number 1W
Distance and direction from nearest town or city: 2 N 4 1/2 W, Valley Center				3 Owner of well: Arlo Norstedt		
Street address of well location if in city:				Address: Sedgwick, Kansas		
Locate with "X" in section below: 		Sketch map: Open field		4 Well depth: 95 ft. Date of completion 3/18/76 Well diameter 30 in.		
2 Type and color of material		From To		5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
				6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐		
				7 Casing: Material Cem-Asb Height: above below Threaded ☐ Welded ☐ Surface 12 in. Dipm. 16 in. to 95 ft. depth! Drive shoe? ☐ Yes ☒ No Weight 35 lbs. (ft)		
				8 Screen: Manufacturer Johnson Type Cem-Asb Dia. 16" Slow gauze 1/4 Length 39 Set between 56 ft. and 95 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 3/8		
				9 Static water level: 35 ft. below land surface Date 2/27/76		
(use a second sheet if needed)				10 Pumping level below land surfaces: no test ____ ft. after ____ hrs. pumping ____ g.p.m. ____ ft. after ____ hrs. pumping ____ g.p.m. Estimated maximum yield 4000 g.p.m.		
				11 Water sample submitted: ☐ Yes ☒ No Date ____		
				12 Well head completion: ☐ Pitless adapter 10 inches above grade		
				13 Well grouted? ☒ Yes ☐ No ☒ Neat cement ☐ Bentonite ☐ ____ Depth: From 0 ft. to 10 ft.		
				14 Nearest source of possible contamination: ft. .5 Direction N Type Domestic Well disinfected upon completion? ☐ Yes ☒ No		
16 Remarks: elevation Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley				15 Pump: ☐ Not installed Manufacturer's name Peerless Model number 15658 HP 25 Volts 230 Length of drop pipe 70 ft. capacity 4000 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
				17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Weninger Drilling 238 Business name W. Weninger License No. 67101 Address Maize, Kansas Signed W. Weninger Date 3/18/76 Authorized representative		

Forward the white, blue and pink copies to the Kansas State Dept. Of Health.

Form WWC-5