


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Fraction 1/4 SE 1/4 SE 1/4	Section number 35	Township number T 25 S R 1	Range number 1
2. Distance and direction from nearest town or city: Street address of well location if in city:		4119 Palos Verde Valley Center, Ks.		3. Owner of well: R.R. or street: City, state, zip code:		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. 11 in. Completion date 12-12-76 Well depth 35 ft.		
5. Type and color of material		From		To		7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary
Topsoil		0		3		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Fine Sand		3		23		9. Casing: Material styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight ☐ lbs./ft. Dia. 5 in. to 35 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. .200
Medium too coarse sand		23		35		10. Screen: Manufacturer's name Sunflower Plastic Type styrene Dia. 5" Slot/groove .06 Length 10' Set between 25 ft. and 35 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 1-1/8"
						11. Static water level: ☐ mo./day/yr. 15 ft. below land surface Date 12-12-76
						12. Pumping level below land surfaces: ft. after ☐ hrs. pumping ☐ g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.
						13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☐ No Date ☐
						14. Well head completion: ☒ Pitless adapter 12 inches above grade
						15. Well grouted? yes With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40" ft. to 14 ft.
						16. Nearest source of possible contamination: Septic Tank ft. 100 Direction East Type Tank Well disinfected upon completion? ☒ Yes ☐ No
						17. Pump: ☐ Not installed Manufacturer's name Sta-Rite Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 25 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
18. Elevation:		19. Remarks: Flat Ground		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 1-8-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5