


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Sedgwick	Section NE 1/4 SE 1/4	Section number 35	Township number T 25 S R 1W	Range number E 1W
2. Distance and direction from nearest town or city: 4010 Rio Grande Street address of well location if in city: Valley Center, Kansas			3. Owner of well: Walt Stauffer Const. R.R. or street: 3535 West 13th City, state, zip code: Wichita, Kansas 67203			
* Locate with "X" in section below: N W E S 1 Mile 1 Mile			Sketch map: 			
5. Type and color of material			From	To	6. Bore hole dia. 11 in. Completion date 6-29-77 Well depth 35 ft.	
Topsoil			0	2	7. Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary	
Clay			2	12	8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Fine Sand			12	20	9. Casing: Material Styrene Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☒ PVC ☐ Weight 11 lbs./ft. Dia. 5 in. to 35 ft. depth Wall Thickness: inches or Dia. 5 in. to 35 ft. depth gage No. 200	
Medium Sand			20	35	10. Screen: Manufacturer's name Sunflower Plastic Type Styrene Dia. 5" Slot 1/16" .06 Length 10' Set between 25 ft. and 35 ft. ft. and 35 ft. Gravel pack? yes Size range of material 1/4-1/8"	
					11. Static water level: 15 ft. below land surface Date 6-29-77 mo./day/yr.	
					12. Pumping level below land surfaces: ft. after 12 hrs. pumping 12 g.p.m. ft. after 12 hrs. pumping 12 g.p.m. Estimated maximum yield 12 g.p.m.	
					13. Water sample submitted: 12 mo./day/yr. ☒ Yes ☐ No Date 6-29-77	
					14. Well head completion: ☒ Pitless adapter 12 inches above grade	
					15. Well grouted? yes to 2 fine sand mix. With: ☐ Neat cement ☐ Bentonite ☒ Concrete Depth: From 40' ft. to 14 ft.	
					16. Nearest source of possible contamination: ft. 12 Direction NE Type NONE Well disinfected upon completion? ☒ Yes ☐ No	
					17. Pump: Manufacturer's name Sta-Rite Not installed Model number 20P4D02 HP 3/4 Volts 230 Length of drop pipe 25 ft. capacity 20 g.p.m. Type: ☒ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
(Use a second sheet if needed)						
18. Elevation: Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley		19. Remarks: Septic System was not installed when the well was drilled. No apparent source for contamination.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Harp Well & Pump 236 Business name License No. Address Wichita, Kansas Signed M. Arnold Date 7-5-77 Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5