


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County: <u>Sedgewick</u>	Fraction: <u>SE 1/4 NW 1/4 SE 1/4</u>	Section number: <u>35</u>	Township number: <u>T 25 S</u>	Range number: <u>R 10 E</u>
2. Distance and direction from nearest town or city:		3. Owner of well: <u>Robt Meyer</u>		R.R. or street: <u>R.R. Garden plain KS 67050</u>		
Street address of well location if in city: <u>8041 Buena Vista Valley Cut KS.</u>		City, state, zip code: <u>Garden plain KS 67050</u>		6. Bore hole dia. <u>3 1/2</u> in. Completion date: <u>10/28/78</u>		
4. Locate with "X" in section below:		Sketch map:		Well depth: <u>35</u> ft.		
				7. ☒ Cable tool ☒ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☐ Reverse rotary		
5. Type and color of material		From To		8. Use: ☒ Domestic ☐ Public supply ☐ Industry ☐ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
<u>Top soil</u>		<u>0 2</u>		9. Casing: Material <u>Stainless</u> Height: <u>Above</u> or below		
<u>red clay</u>		<u>2 8</u>		Threaded ☐ Welded ☒ Surface <u>12</u> in.		
<u>fine sand</u>		<u>8 19</u>		RMP ☒ PVC ☐ Weight <u>1.50</u> lbs./ft.		
<u>red clay</u>		<u>19 21</u>		Dia. <u>5</u> in. to <u>35</u> ft. depth Wall Thickness: inches or		
<u>med gravel</u>		<u>21 35</u>		Dia. <u>5</u> in. to <u>35</u> ft. depth gage No. <u>1200</u>		
				10. Screen: Manufacturer's name <u>Sunflower</u>		
				Type <u>200</u> Dia. <u>5</u> in.		
				Slot gauge <u>1/16</u> Length <u>8</u> ft.		
				Set between <u>24</u> ft. and <u>35</u> ft.		
				Gravel pack <u>yes</u> Size range of material <u>3/8</u>		
				11. Static water level: <u>13</u> ft. below land surface Date <u>10/28/78</u>		
				12. Pumping level below land surfaces:		
				<u>15</u> ft. after <u>12</u> hrs. pumping <u>15</u> g.p.m.		
				<u>15</u> ft. after <u>12</u> hrs. pumping <u>15</u> g.p.m.		
				Estimated maximum yield <u>50-60</u> g.p.m.		
				13. Water sample submitted: <u>no.</u> /day/yr.		
				☐ Yes ☒ No Date <u>10/28/78</u>		
				14. Well head completion:		
				☐ Pitless adapter <u>12</u> inches above grade		
				15. Well grouted? <u>yes</u> ☒		
				With: ☐ Neat cement ☐ Bentonite ☒ Concrete		
				Depth: From <u>6</u> ft. to <u>16</u> ft.		
				16. Nearest source of possible contamination		
				<u>80</u> ft. Direction <u>SE</u> Type <u>Septic</u>		
				Well disinfected upon completion? ☒ Yes ☐ No		
				17. Pump:		
				☒ Not installed		
				Manufacturer's name <u>Lawrence</u>		
				Model number <u>318</u> HP <u>1</u> Volts <u>115</u>		
				Length of drop pipe <u>35</u> ft. capacity <u>15</u> g.p.m.		
				Type:		
				☐ Submersible ☐ Turbine		
				☐ Jet ☐ Reciprocating		
				☐ Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification:		
Topography:				This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief.		
☒ Hill				Business name <u>Lawrence</u> License No. <u>318</u>		
☐ Slope				Address <u>Lawrence</u>		
☐ Upland				Signed <u>Lawrence</u> 10/28/78		
☐ Valley				Authorized representative		

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5