

(4)

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Reno</u>	<u>NE</u> $\frac{1}{4}$ <u>NW</u> $\frac{1}{4}$ <u>NW</u> $\frac{1}{4}$	<u>4</u>	<u>T</u> <u>25</u> <u>S</u>	<u>R</u> <u>10</u> <u>W</u>

Distance and direction from nearest town or city street address of well if located within city?

3 Miles South $\frac{1}{4}$ Mi West Of Sylvia, Kansas2 WATER WELL OWNER: Cattleman Feed YardRR#, St. Address, Box #: Box 248

Board of Agriculture, Division of Water Resources

City, State, ZIP Code: Turon, Kans. 67583

Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL: 66 ft. ELEVATION:Depth(s) Groundwater Encountered 1. 21' ft. 2. ft. 3. ft.WELL'S STATIC WATER LEVEL 22'6" ft. below land surface measured on mo/day/yr Mar 3 95

Pump test data: Well water was ft. after hours pumping gpm

Est. Yield 20 gpm: Well water was ft. after hours pumping gpmBore Hole Diameter 7 7/8" in. to 66' ft. and in. to ft.

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well

☒ Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)

2 Irrigation 4 Industrial 7 Lawn and garden only 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submittedWater Well Disinfected? Yes ☒ No

5 TYPE OF BLANK CASING USED:

5 Wrought iron

8 Concrete tile

CASING JOINTS: Glued ☒ Clamped

1 Steel

3 RMP (SR)

6 Asbestos-Cement

9 Other (specify below)

Welded

☒ 2 PVC

4 ABS

7 Fiberglass

Threaded

Blank casing diameter 5" in. to 56' ft. Dia in. to ft. Dia in. to ft.Casing height above land surface 14" in. weight 160 lbs./ft. Wall thickness or gauge No. Sdr 26

TYPE OF SCREEN OR PERFORATION MATERIAL:

1 Steel

3 Stainless steel

5 Fiberglass

☒ PVC

10 Asbestos-cement

2 Brass

4 Galvanized steel

6 Concrete tile

8 RMP (SR)

11 Other (specify)

9 ABS

12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot

3 Mill slot

5 Gauzed wrapped

☒ Saw cut

11 None (open hole)

2 Louvered shutter

4 Key punched

6 Wire wrapped

9 Drilled holes

2 Louvered shutter

4 Key punched

7 Torch cut

10 Other (specify)

SCREEN-PERFORATED INTERVALS: From 66 ft. to 56' ft. From ft. to ft.

From ft. to ft. From ft. to ft.

GRAVEL PACK INTERVALS: From ft. to ft. From ft. to ft.

From 30' ft. to 66' ft. From ft. to ft.

6 GROUT MATERIAL:

1 Neat cement

2 Cement grout

☒ 3 Bentonite

4 Other

Grout Intervals: From 7' ft. to 30' ft. From ft. to ft. From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank

4 Lateral lines

7 Pit privy

10 Livestock pens

14 Abandoned water well

☒ 2 Sewer lines

5 Cess pool

8 Sewage lagoon

11 Fuel storage

15 Oil well/Gas well

3 Watertight sewer lines

6 Seepage pit

9 Feedyard

12 Fertilizer storage

16 Other (specify below)

13 Insecticide storage

Direction from well?

South

How many feet?

5280'

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0'	8'	Top Soil.			
8'	20'	Clay.			
20'	21'	Lime.			
21'	40'	Course sand (Dirty)			
40'	45'	Fine Sand.			
45'	50'	Medium Course sand.			
50'	64'	Course sand & Fine Gravel,			
64'	66'	Clay.			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) Mar. 3-95 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 112 This Water Well Record was completed on (mo/day/yr) Mar 25 - 95 under the business name of Wells Drilling Co. by (signature) Del Wells

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone: 913-296-5545. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY

T

R

EW

SEC.

1/4

1/4

1/4