

1 LOCATION OF WATER WELL: County: Stafford		Fraction 1/4 SW 1/4 NW 1/4 NE 1/4		Section Number 26	Township No. T 25 S	Range Number R 11 ☐ E ☒ W																																																																		
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 3 3/4 miles west and 3 1/4 miles north of Turon				Global Positioning System (GPS) information: Latitude: 37.849894 (in decimal degrees) Longitude: -98.498916 (in decimal degrees) Elevation: unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																				
2 WATER WELL OWNER: Larry Zink RR#, Street Address, Box #: 733 SE 140th Ave. City, State, ZIP Code: Turon, KS 67583-9222																																																																								
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N W <table border="1" style="display: inline-table; border-collapse: collapse;"><tr><td style="padding: 5px;">--NW--</td><td style="padding: 5px; text-align: center;">X</td><td style="padding: 5px;">--NE--</td></tr><tr><td style="padding: 5px;">--SW--</td><td style="padding: 5px;"></td><td style="padding: 5px;">--SE--</td></tr></table> E S -----1 mile-----		--NW--	X	--NE--	--SW--		--SE--	4 DEPTH OF COMPLETED WELL 108 ft. Depth(s) Groundwater Encountered (1) _____ ft. (2) _____ ft. (3) _____ ft. WELL'S STATIC WATER LEVEL 10.52 ft. below land surface measured on mo/day/yr 3/29/10 Pump test data: Well water was not checked ft. after _____ hours pumping _____ gpm EST. YIELD unknown gpm. Well water was _____ ft. after _____ hours pumping _____ gpm Bore Hole Diameter 6 in. to 110 ft., and _____ in. to _____ ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Observation Well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted _____ Water well disinfected? ☒ Yes ☐ No																																																																
--NW--	X	--NE--																																																																						
--SW--		--SE--																																																																						
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 2 1/2 in. to 100 ft., Diameter _____ in. to _____ ft., Diameter _____ in. to _____ ft. Casing height above land surface 36 in., Weight 1.10 lbs./ft., Wall thickness or gauge No. 203 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 100 ft. to 105 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From 94 ft. to 110 ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.																																																																								
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From _____ ft. to _____ ft., From 0 ft. to 94 ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None known Direction from well _____ Distance from well _____																																																																								
<table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>FROM</th><th>TO</th><th>LITHOLOGIC LOG</th><th>FROM</th><th>TO</th><th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th></tr></thead><tbody><tr><td>0</td><td>6</td><td>Topsoil</td><td>79</td><td>89</td><td>Sand and gravel, coarse to fine, clean</td></tr><tr><td>6</td><td>11</td><td>Clay, tan and white, hard</td><td>89</td><td>90</td><td>Clay, tan, hard</td></tr><tr><td>11</td><td>17</td><td>Clay, white, sandy, hard</td><td>90</td><td>110</td><td>Sand, coarse to very fine, with gravel, fine, clean and loose</td></tr><tr><td>17</td><td>31</td><td>Sand and gravel, medium to fine, clean</td><td></td><td></td><td></td></tr><tr><td>31</td><td>49</td><td>Sand and gravel, coarse to fine, clean</td><td></td><td></td><td></td></tr><tr><td>49</td><td>51</td><td>Clay, tan, hard</td><td></td><td></td><td></td></tr><tr><td>51</td><td>68</td><td>Sand and gravel, coarse to fine, clean</td><td></td><td></td><td></td></tr><tr><td>68</td><td>73</td><td>Clay, brown and white, hard</td><td></td><td></td><td></td></tr><tr><td>73</td><td>78</td><td>Sand and gravel, medium to fine, clean</td><td></td><td></td><td></td></tr><tr><td>78</td><td>79</td><td>Clay, tan and brown, hard</td><td></td><td></td><td></td></tr></tbody></table>							FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	6	Topsoil	79	89	Sand and gravel, coarse to fine, clean	6	11	Clay, tan and white, hard	89	90	Clay, tan, hard	11	17	Clay, white, sandy, hard	90	110	Sand, coarse to very fine, with gravel, fine, clean and loose	17	31	Sand and gravel, medium to fine, clean				31	49	Sand and gravel, coarse to fine, clean				49	51	Clay, tan, hard				51	68	Sand and gravel, coarse to fine, clean				68	73	Clay, brown and white, hard				73	78	Sand and gravel, medium to fine, clean				78	79	Clay, tan and brown, hard			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																			
0	6	Topsoil	79	89	Sand and gravel, coarse to fine, clean																																																																			
6	11	Clay, tan and white, hard	89	90	Clay, tan, hard																																																																			
11	17	Clay, white, sandy, hard	90	110	Sand, coarse to very fine, with gravel, fine, clean and loose																																																																			
17	31	Sand and gravel, medium to fine, clean																																																																						
31	49	Sand and gravel, coarse to fine, clean																																																																						
49	51	Clay, tan, hard																																																																						
51	68	Sand and gravel, coarse to fine, clean																																																																						
68	73	Clay, brown and white, hard																																																																						
73	78	Sand and gravel, medium to fine, clean																																																																						
78	79	Clay, tan and brown, hard																																																																						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 3/29/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 3/30/10 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>[Signature]</i>																																																																								
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																								