

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: <u>Stafford</u>	NW 1/4 NW 1/4 NW 1/4	15	T 25 S	R 11 X W

Distance and direction from nearest town or city street address of well if located within city?

Approx. 5 miles south and 4 miles east of Stafford, KS

2 WATER WELL OWNER:	Ralph Weller	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # :	2500 Pheasant	Application Number: <u>not required</u>
City, State, ZIP Code :	Great Bend, KS 67530	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 89 ft. ELEVATION: unknown
	Depth(s) Groundwater Encountered 1. 14 ft. 2. ft. 3. ft. WELL'S STATIC WATER LEVEL 14 ft. below land surface measured on mo/day/yr 6/29/83 Pump test data: Well water was <u>not ck'd</u> ft. after hours pumping gpm Est. Yield <u>unknown</u> gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 9 in. to 89 ft. and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well Was a chemical/bacteriological sample submitted to Department? Yes No <u>X</u> ; If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes <u>X</u> No

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: <u>Glued XX</u> Clamped
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below)
2 <u>PVC</u>	4 ABS	7 Fiberglass	Welded
Blank casing diameter 5 in. to 74 ft. Dia			Threaded
Casing height above land surface 24 in. weight 2.277 lbs./ft. Wall thickness or gauge No. 214			
TYPE OF SCREEN OR PERFORATION MATERIAL:	7 <u>PVC</u>	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 <u>Drilled holes</u>
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify)
SCREEN-PERFORATED INTERVALS:	From 74 ft. to 89 ft.	From ft. to ft.	
GRAVEL PACK INTERVALS:	From 25 ft. to 89 ft.	From ft. to ft.	
ANNULAR FILL	From 10 ft. to 21 ft.	From ft. to ft.	

6 GROUT MATERIAL:	1 <u>Neat cement</u>	2 Cement grout	3 Bentonite	4 Other
Grout Intervals:	From 0 ft. to 10 ft.	From 21 ft. to 25 ft.	From ft. to ft.	
What is the nearest source of possible contamination:	1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens
	2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage
	3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage
				13 Insecticide storage
Direction from well? <u>Southeast</u>				14 Abandoned water well
				15 Oil well/Gas well
				16 Other (specify below)
				How many feet? <u>125'</u>

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	13 <u>04</u>	Fine sand, topsoil & sandy brown clay			
13	28 <u>17</u>	Sand & gravel, med. some coarse			
28	32 <u>01</u>	Tan clay			
32	37 <u>17</u>	Sand & gravel, very fine to fine			
37	45 <u>01</u>	Brown clay w/caliche			
45	56 <u>17</u>	Sand & gravel, fine, some med.			
56	70 <u>04</u>	Brown, clay some sandy			
70	89 <u>17</u>	Sand & gravel, fine clean w/streak of clay at 80'			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) <u>constructed</u> , (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 6-29-83 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185. This Water Well Record was completed on (mo/day/yr) 7-13-83 under the business name of <u>Clarke Well & Eq., Inc.</u> by (signature) <u>[Signature]</u>
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.