

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County Stafford	Fraction 1/4 1/4 CNE 1/4	Section number 20	Township number T 25 S	Range number R 11 E						
2. Distance and direction from nearest town or city: 9 miles Southeast of Stafford Street address of well location if in city:			3. Owner of well: Lawrence Debes R.R. or street: Box 1206 City, state, zip code: Great Bend, KS								
4. Locate with "X" in section below: N 1 Mile W <table border="1" style="display: inline-table; vertical-align: middle;"><tr><td> </td><td> </td></tr><tr><td>NW</td><td>NE</td></tr><tr><td>SW</td><td>SE</td></tr></table> E S 1 Mile					NW	NE	SW	SE	Sketch map:		
NW	NE										
SW	SE										
5. Type and color of material			From	To	6. Bore hole dia. 24 in. Completion date 5-25-76 Well depth 67 ft.						
sandy top soil			0	2	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary						
gray & brown clay			2	18	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other						
sand			18	22	9. Casing: Material steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 40 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.						
gray clay			22	24	10. Screen: Manufacturer's name Doerr from 40-52 & Johnson at 52-67 Type Double-slot Dia. 16" ☒ Slot gauze 1/8" Length 27 Set between 40 ft. and 52 ft. 52 ft. and 67 ft. Gravel pack? yes Size range of material 3/8-200						
sand & gravel			24	56	11. Static water level: ☐ mo./day/yr. 19 ft. below land surface Date 4-29-76						
brown clay			56	60	12. Pumping level below land surfaces: ft. after ☐ hrs. pumping N/C g.p.m. ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.						
sand & gravel & clay streaks			60	64	13. Water sample submitted: ☐ mo./day/yr. Yes ☒ No ☐ Date ☐						
brown clay			64	67	14. Well head completion: ☐ Pitless adapter 12 inches above grade						
					15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.						
					16. Nearest source of possible contamination: ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No						
					17. Pump: ☐ Not installed Manufacturer's name FMC-Peerless Model number 12LB-3 HP 80 Volts --- Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other						
(Use a second sheet if needed)											
18. Elevation: Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley	19. Remarks: Both men in XX Block #3 are Owners of the well.		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq. Inc. 185 Business name Great Bend, KS License No. 67530 Address 6-4-76 Signed [Signature] Date 6-4-76 Authorized representative								

25 110 20 1/4 1/4 1/4 CNE