

1 LOCATION OF WATER WELL:	Fraction	Near Center	Section Number	Township Number	Range Number
County: Stafford	1/4 NW 1/4	1/4 NW 1/4	22	T 25 S	R 11

EW

Distance and direction from nearest town or city street address of well if located within city?

Approx. 6 miles south and 4 1/4 miles east of Stafford, Ks.

2 WATER WELL OWNER: Max Nichols	Board of Agriculture, Division of Water Resources
RR#, St. Address, Box #: P.O. Box 515	Application Number: 38,874
City, State, ZIP Code: Great Bend, Kansas 67530	

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:	4 DEPTH OF COMPLETED WELL: 99' ft. ELEVATION: unknown
	Depth(s) Groundwater Encountered 1. 33' ft. 2. ft. 3. ft.
	WELL'S STATIC WATER LEVEL 33 ft. below land surface measured on mo/day/yr 8-18-88
	Pump test data: Well water was not ck'd ft. after hours pumping gpm
	Est. Yield 1,100 gpm: Well water was ft. after hours pumping gpm
	Bore Hole Diameter 24" in. to 97' ft. and in. to ft.
WELL WATER TO BE USED AS:	5 Public water supply 8 Air conditioning 11 Injection well
1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)	
2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well	
Was a chemical/bacteriological sample submitted to Department? Yes.....No.....X.....; If yes, mo/day/yr sample was submitted	Water Well Disinfected? Yes No X

5 TYPE OF BLANK CASING USED:	5 Wrought iron	8 Concrete tile	CASING JOINTS: Glued.....Clamped.....
1 Steel	3 RMP (SR)	6 Asbestos-Cement	9 Other (specify below) Welded. X
2 PVC	4 ABS	7 Fiberglass	Threaded.....
Blank casing diameter 16 in. to 57.5 ft., Dia			
Casing height above land surface 18 in., weight 42.05 lbs./ft. Wall thickness or gauge No. 250			
TYPE OF SCREEN OR PERFORATION MATERIAL:	7 PVC	10 Asbestos-cement	
1 Steel	3 Stainless steel	5 Fiberglass	8 RMP (SR)
2 Brass	4 Galvanized steel	6 Concrete tile	9 ABS
SCREEN OR PERFORATION OPENINGS ARE:	5 Gauzed wrapped	8 Saw cut	11 None (open hole)
1 Continuous slot	3 Mill slot	6 Wire wrapped	9 Drilled holes
2 Louvered shutter	4 Key punched	7 Torch cut	10 Other (specify) Doerr bridge slot
SCREEN-PERFORATED INTERVALS:	From 57.5 ft. to 97.5 ft.		
	From ft. to ft.		
GRAVEL PACK INTERVALS:	From 20 ft. to 97 ft.		
	From ft. to ft.		

6 GROUT MATERIAL:	1 Neat cement	2 Cement grout	3 Bentonite	4 Other
Grout Intervals:	From 0 ft. to 20 ft.			
What is the nearest source of possible contamination:				
1 Septic tank	4 Lateral lines	7 Pit privy	10 Livestock pens	14 Abandoned water well
2 Sewer lines	5 Cess pool	8 Sewage lagoon	11 Fuel storage	15 Oil well/Gas well
3 Watertight sewer lines	6 Seepage pit	9 Feedyard	12 Fertilizer storage	16 Other (specify below)
			13 Insecticide storage	no known source
Direction from well?			How many feet?	

FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	40	fine sand topsoil and sandy brown and white clay.			
40	97	sand and gravel medium to fine, some coarse with few clay streaks 75' to 78'			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 8-18-88 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/yr) 8-26-88 under the business name of Clarke Well & Equipment Co., Inc. by (signature) [Signature]
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water Protection, Topeka, Kansas 66620-7320, Telephone: 913-862-9360. Send one to WATER WELL OWNER and retain one for your records.