

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction Center of 1/4 XXXE 1/2 XXX	Section number 32	Township number T 25 S	Range number R 11
2. Distance and direction from nearest town or city: 10 1/2 miles Southeast of Stafford, KS Street address of well location if in city:				3. Owner of well: Gilbert Rundell R.R. or street: Route, Box 128 City, state, zip code: Stafford, KS 67578		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. XX 24 . Completion date 5-13-77 Well depth 72 ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
Top soil		0	3	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
Brown & gray clay & limestone streaks		3	37	9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>42</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7 ga.</u>		
Sand & gravel & clay streaks at 59'		37	72	10. Screen: Manufacturer's name <u>D-Doerr & C-Cook</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot/gauze <u>1/8</u> Length <u>D-20' & C-</u> Set between <u>D 42</u> ft. and <u>62</u> ft. <u>62</u> ft. and <u>72</u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u>		
				11. Static water level: <u>28</u> ft. below land surface Date <u>5-3-77</u> mo./day/yr.		
				12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.		
				13. Water sample submitted: <u> </u> mo./day/yr. <u>Yes</u> ☒ <u>No</u> ☐ Date <u> </u>		
				14. Well head completion: <u> </u> Pitless adapter <u>12</u> Inches above grade		
				15. Well grouted? <u>yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.		
				16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No ☐		
				17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless Pump</u> Model number <u>12LB-3</u> HP <u>80</u> Volts <u> </u> Length of drop pipe <u>60</u> ft. capacity <u>900</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet ☐ Reciprocating <u> </u> Centrifugal ☐ Other		
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u> </u> Address <u> </u> Signed <u> </u> 5-16-77 Authorized representative		