

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

1 LOCATION OF WATER WELL: County: Stafford		Fraction 1/4 NE 1/4 SW 1/4 SW 1/4		Section Number 34	Township No. T 25 S	Range Number R 12 ☐ E ☒ W																																																																		
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ Approximately 4 miles west and 4 3/4 miles north of Preston				Global Positioning System (GPS) information: Latitude: 37.827803 (in decimal degrees) Longitude: -98.633541 (in decimal degrees) Elevation: unknown Datum: ☐ WGS 84, ☒ NAD 83, ☐ NAD 27 Collection Method: ☒ GPS unit (Make/Model: WAAS) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☒ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																				
2 WATER WELL OWNER: Joan Clark RR#, Street Address, Box #: 70056 NE 110th St. City, State, ZIP Code : Preston, KS 67569																																																																								
3 LOCATE WELL WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 98 ft. Depth(s) Groundwater Encountered (1) 11.3 ft. (2) 11.3 ft. (3) 11.3 ft. WELL'S STATIC WATER LEVEL 11.3 ft. below land surface measured on mo/day/yr 3/18/10 Pump test data: Well water was not checked ft. after 0 hours pumping 0 gpm EST. YIELD unknown gpm. Well water was 0 ft. after 0 hours pumping 0 gpm Bore Hole Diameter 6 in. to 98 ft., and 0 in. to 0 ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☒ Other (Specify below) ☐ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Observation Well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted 0 Water well disinfected? ☒ Yes ☐ No																																																																						
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other _____ CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 2 1/2 in. to 91 ft., Diameter 0 in. to 0 ft., Diameter 0 in. to 0 ft. Casing height above land surface 24 in., Weight 1.10 lbs./ft., Wall thickness or gauge No. 203 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) _____ ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☒ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) _____ SCREEN-PERFORATED INTERVALS: From 91 ft. to 96 ft., From 0 ft. to 0 ft. From 89 ft. to 98 ft., From 0 ft. to 0 ft. GRAVEL PACK INTERVALS: From 89 ft. to 98 ft., From 0 ft. to 0 ft. From 0 ft. to 0 ft., From 0 ft. to 0 ft.																																																																								
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other _____ Grout Intervals: From 0 ft. to 89 ft., From 0 ft. to 89 ft., From 0 ft. to 0 ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☒ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well Irrigation Well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well North Distance from well 10'																																																																								
<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>3</td> <td>Topsoil</td> <td></td> <td></td> <td></td> </tr> <tr> <td>3</td> <td>27</td> <td>Clay, tan, sandy</td> <td></td> <td></td> <td></td> </tr> <tr> <td>27</td> <td>50</td> <td>Sand and gravel, fine to coarse</td> <td></td> <td></td> <td></td> </tr> <tr> <td>50</td> <td>69</td> <td>Sand and gravel, fine to medium</td> <td></td> <td></td> <td></td> </tr> <tr> <td>69</td> <td>74</td> <td>Clay, gray, brown, hard</td> <td></td> <td></td> <td></td> </tr> <tr> <td>74</td> <td>83</td> <td>Clay, brown, sandy</td> <td></td> <td></td> <td></td> </tr> <tr> <td>83</td> <td>96</td> <td>Sand and gravel, fine to medium</td> <td></td> <td></td> <td></td> </tr> <tr> <td>96</td> <td>98</td> <td>Clay, gray</td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>							FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	3	Topsoil				3	27	Clay, tan, sandy				27	50	Sand and gravel, fine to coarse				50	69	Sand and gravel, fine to medium				69	74	Clay, gray, brown, hard				74	83	Clay, brown, sandy				83	96	Sand and gravel, fine to medium				96	98	Clay, gray															
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																			
0	3	Topsoil																																																																						
3	27	Clay, tan, sandy																																																																						
27	50	Sand and gravel, fine to coarse																																																																						
50	69	Sand and gravel, fine to medium																																																																						
69	74	Clay, gray, brown, hard																																																																						
74	83	Clay, brown, sandy																																																																						
83	96	Sand and gravel, fine to medium																																																																						
96	98	Clay, gray																																																																						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 3/18/10 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 185 This Water Well Record was completed on (mo/day/year) 3/19/10 under the business name of Clarke Well & Equipment, Inc. by (signature) [Signature]																																																																								
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																								