

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 1/4 CSW 1/4	Section number 3	Township number T 25 S R 12 E	Range number W
2. Distance and direction from nearest town or city: 6 mi. Southwest of Stafford, KS Street address of well location if in city:				3. Owner of well: Merlyn Hearn R.R. or street: Route 1 City, state, zip code: Stafford, KS 67578		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile				6. Bore hole dia. 24 in. Completion date 9-18-75 Well depth 131 ft. 7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary 8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other 9. Casing: Material Steel Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 68 ft. depth Wall Thickness: inches or Dia. 16 in. to 98 ft. depth gage No. 7 ga. 10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot gauge 1/8 Length 43' Set between 68 ft. and 78 ft. 98 ft. and 131 ft. Gravel pack? Yes Size range of material 3/8-200 11. Static water level: _____ mo./day/yr. 25 ft. below land surface Date 9-18-75 12. Pumping level below land surfaces: N/C _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m. 13. Water sample submitted: _____ mo./day/yr. Yes ☒ No ☐ Date _____ 14. Well head completion: Pitless adapter 12 Inches above grade 15. Well grouted? Yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft. 16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? Yes ☐ No ☒ 17. Pump: ☒ Not installed Manufacturer's name _____ Model number _____ HP _____ Volts _____ Length of drop pipe _____ ft. capacity _____ g.p.m. Type: ☐ Submersible ☐ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
5. Type and color of material				From	To	
Top soil				0	2	
Sand & sandy clay				2	10	
Brown & white white clay & limestone				10	33	
Sand & gravel				33	47	
Brown & gray clay & limestone				47	68	
Sand & gravel				68	75	
Gray & white clay & limestone				75	102	
Sand, gravel & clay streak at 120'				102	131	
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name _____ License No. _____ Address Great Bend, KS Signed [Signature] Date 9-18-75 Authorized representative		
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						