


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County <u>Stafford</u>	Fraction <u>SW 1/4 NE 1/4 SW 1/4</u>	Section number <u>15</u>	Township number <u>T 25 S</u>	Range number <u>R 12 W E/W</u>
2. Distance and direction from nearest town or city: <u>6.5 2 W</u> Street address of well location if in city: <u>of Stafford, Ks</u>				3. Owner of well: <u>MORLYN HEARN</u> R.R. or street: City, state, zip code: <u>STAFFORD, KS</u>		
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <u>30</u> in. Completion date <u>7 June 79</u> Well depth <u>90</u> ft.		
				7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
5. Type and color of material				From	To	8. Use: Domestic ☐ Public supply ☐ Industry ☐ ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other ☐
<u>SILT, SANDY</u>				<u>0</u>	<u>6</u>	9. Casing: Material <u>STL</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. <u>16</u> in. to <u>46</u> ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. <u>188</u>
<u>Clay, Tan & green</u>				<u>6</u>	<u>24</u>	10. Screen: Manufacturer's name <u>DOERR</u> Type ☐ Dia. <u>16"</u> Slot/gauze <u>1/8</u> Length <u>44'</u> Set between <u>46</u> ft. and <u>90</u> ft. ft. and ☐ ft. Gravel pack? ☒ Size range of material <u>1/4" x 3/8"</u>
<u>SAND, Fine to Coarse & Coarse gravel</u>				<u>24</u>	<u>42</u>	11. Static water level: ☐ mo./day/yr. <u>16</u> ft. below land surface Date <u>7 June 79</u>
<u>CLAY, TAN</u>				<u>42</u>	<u>46</u>	12. Pumping level below land surfaces: <u>39</u> ft. after <u>1</u> hrs. pumping <u>800</u> g.p.m. <u>45</u> ft. after <u>1</u> hrs. pumping <u>1000</u> g.p.m. Estimated maximum yield <u>1400</u> g.p.m.
<u>SAND, Fine to Coarse & med gravel</u>				<u>46</u>	<u>76</u>	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date <u>7 June 79</u>
<u>CLAY, Tan & green</u>				<u>76</u>	<u>80</u>	14. Well head completion: ☐ Pitless adapter <u>12</u> inches above grade
<u>SAND, Fine to Coarse & med gravel</u>				<u>80</u>	<u>122</u>	15. Well grouted? ☒ With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.
<u>SHALE, RED</u>				<u>122</u>	<u>140</u>	16. Nearest source of possible contamination: <u>NONE</u> ft. Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No
						17. Pump: ☐ Not installed Manufacturer's name <u>Simmons</u> Model number <u>60</u> HP <u>60</u> Volts <u>240</u> Length of drop pipe <u>60</u> ft. capacity <u>800</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
						20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Central Well & Pump 325</u> Business name <u>Box 1032 Pratt, KS</u> License No. <u>1/4 1/4 1/4</u> Address <u>Box 1032 Pratt, KS</u> Signed <u>W. Honanell</u> Date <u>20 June 79</u> Authorized representative
18. Elevation:		19. Remarks: <u>5' x 14' x 8" concrete slab poured at surface</u>				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						