


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:	County: STAFFORD	Fraction: SE 1/4 NW 1/4 SE 1/4	Section number: 16	Township number: T 25 S	Range number: R 12 W E/W
2. Distance and direction from nearest town or city: 65 2 W Street address of well location if in city: STAFFORD, KS			3. Owner of well: MERLYN HEARN R.R. or street: City, state, zip code: STAFFORD, KS		
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile Sketch map: 			6. Bore hole dia. 30 in. Completion date 7 JUNE 79 Well depth 90 ft.		
			7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☒ Bored ☒ Reverse rotary		
			8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
			9. Casing: Material STL Height: Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☒ Weight 15 lbs./ft. Dia. 16 in. to 42 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 188		
5. Type and color of material			From	To	10. Screen: Manufacturer's name DOERR
SILT, SANDY			0	4	Type ☐ Dia. 16"
CLAY, GREEN & WHITE			4	20	Slot/gauze 1/2 Length 48'
SAND, Fine to Coarse & med gravel			20	31	Set between 42 ft. and 90 ft.
CLAY, TAN			31	42	Gravel pack? ☒ Size range of material 1/2 X 3/8
SAND, Fine to Coarse & med gravel			42	70	11. Static water level: 12 ft. below land surface Date 7 JUNE 79
SAND, Fine to Coarse & Coarse gravel			70	124	12. Pumping level below land surfaces: 31 ft. after 1 hrs. pumping 800 g.p.m. 36 ft. after 1 hrs. pumping 1000 g.p.m. Estimated maximum yield 1400 g.p.m.
SHALE, RED			124	140	13. Water sample submitted: ☒ Yes ☐ No Date
					14. Well head completion: ☐ Pitless adapter 12 inches above grade
					15. Well grouted? ☒ With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.
					16. Nearest source of possible contamination: NONE ft. Direction Type Well disinfected upon completion? ☒ Yes ☐ No
					17. Pump: Manufacturer's name Simmons Not installed Model number HP 60 Volts Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other
(Use a second sheet if needed)					
18. Elevation: Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley	19. Remarks: 5' x 14' x 8" Concrete Slab poured at Surface				
20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Central Well & Pump 325 Business name Address Box 1032 Pratt KS License No. Signed John Horne Date 20 June 79 Authorized representative					

T 25 S R 12 W SE 1/4 NW 1/4 SE 1/4