


1. Location of well: Stafford		County Fraction 1/4 1/4 CNW/4		Section number 21		Township number T 25 S R 12		Range number EW	
2. Distance and direction from nearest town or city: 9 miles Southwest of Stafford, KS Street address of well location if in city:				3. Owner of well: H. Lee Turner R.R. or street: Route 1 City, state, zip code: Great Bend, KS 67530					
4. Locate with "X" in section below:  Sketch map: 1 Mile				6. Bore hole dia. <u>24</u> in. Completion date <u>3-30-77</u> Well depth <u>70</u> ft.					
				7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary					
				8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other					
				9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>30</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7 ga.</u>					
5. Type and color of material				From		To		10. Screen: Manufacturer's name <u>Cook</u>	
Top soil				0		2		Type <u>Cook Screen</u> Dia. <u>16"</u>	
Gray clay & limestone streaks				2		18		Slot gauze <u>1/8</u> Length <u>40'</u>	
Sand & gravel & thin clay streaks				18		46		Set between <u>30</u> ft. and <u>70</u> ft. ft. and <u> </u> ft.	
White clay				46		48		Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u>	
Sand & gravel & clay streaks at 69'				48		70		11. Static water level: <u>16</u> ft. below land surface Date <u>3-17-77</u>	
								12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.	
								13. Water sample submitted: <u> </u> mo./day/yr. ☒ Yes ☐ No Date <u>2-14-77</u>	
								14. Well head completion: <u> </u> Pitless adapter <u>12</u> inches above grade	
								15. Well grouted? <u>yes</u> With: ☒ Neat cement <u> </u> Bentonite <u> </u> Concrete <u> </u> Depth: From <u>0</u> ft. to <u>10</u> ft.	
								16. Nearest source of possible contamination: <u>Field</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No	
								17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless Pump</u> Model number <u>12LB-4</u> HP <u>80</u> Volts <u> </u> Length of drop pipe <u>60</u> ft. capacity <u>900</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet <u> </u> Reciprocating <u> </u> Centrifugal <u> </u> Other	
18. Elevation:				19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u>Great Bend, KS 67530</u> License No. <u> </u> Address <u> </u> Date <u>4-8-77</u> Signed <u>D.W. Clarke</u> Authorized representative			