

WATER WELL RECORD
KSA 82g-1201-1215

Kansas State Dept. Of Health
(Water Well Contractors)
Forbes-Bldg. 740
Topeka, Kansas 66620

1 Location of well:		County Stafford	Township name Union	Fraction SW 1/4 NE 1/4 SW 1/4	Section number 35	Town number 25-S	Range number 12-W																														
Distance and direction from nearest town or city: 8 S 3/4 1 1/2 N				3 Owner of well: Norman Hildebrand																																	
Street address of well location if in city: Stafford				Address: Stafford, Ks. RR 1 67578																																	
Locate with "X" in section below: N W E S				Sketch map:																																	
2 <table border="1" style="width:100%; border-collapse: collapse;"><thead><tr><th>Type and color of material</th><th>From</th><th>To</th></tr></thead><tbody><tr><td>Soil.</td><td>0</td><td>2</td></tr><tr><td>Clay.</td><td>2</td><td>30</td></tr><tr><td>Sandy Clay.</td><td>30</td><td>50</td></tr><tr><td>Gravel</td><td>50</td><td>87</td></tr><tr><td>Clay</td><td>87</td><td>90</td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr><tr><td> </td><td> </td><td> </td></tr></tbody></table>				Type and color of material	From	To	Soil.	0	2	Clay.	2	30	Sandy Clay.	30	50	Gravel	50	87	Clay	87	90													4 Well depth 87 ft. Date of completion 5/19/74 Well diameter _____ in.			
				Type and color of material	From	To																															
				Soil.	0	2																															
				Clay.	2	30																															
				Sandy Clay.	30	50																															
				Gravel	50	87																															
				Clay	87	90																															
5 ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary																																					
6 Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Commercial ☐ Test well ☐ _____																																					
7 Casing: Material steel Height: above/below Threaded ☐ Welded ☒ Surface 12 in. Diam. 57 Weight 30 lbs./ft. 16 in. to 57 ft. depth Drive shoe? ☐ Yes ☒ No _____ in. to _____ ft. depth																																					
8 Screen: Manufacturer Parre Type Lower Dia. 16 Slot/gauze 3/16 Length _____ Set between 57 ft. and 87 ft. Fittings: Gravel pack ☒ Yes ☐ No Size range of material 1/8																																					
9 Static water level: 32 ft. below land surface Date 8/29/74																																					
10 Pumping level below land surfaces: 60 ft. after 1 hrs. pumping 900 g.p.m. 56 ft. after 1/2 hrs. pumping 700 g.p.m. Estimated maximum yield 950 g.p.m.																																					
11 Water sample submitted: ☒ Yes ☐ No Date 9/5/74																																					
12 Well head completion: ☐ Pitless adapter 12 inches above grade																																					
13 Well grouted? ☒ Yes ☐ No ☐ Neat cement ☒ Bentonite ☐ _____ Depth: From 2 ft. to 10 ft.																																					
14 Nearest source of possible contamination: ft. 800 Direction S W Type oil Well disinfected upon completion? ☐ Yes ☒ No																																					
15 Pump: ☐ Not installed Manufacturer's name Jacuzzi Model number 4-12LS HP 60 Volts _____ Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other																																					
16 Remarks: elevation Topography: ☐ Hill ☒ Slope ☐ Upland ☐ Valley																																					
17 Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Darling Drilling Co. 189 Business name License No. _____ Address 1121 West 11th Hutchinson Signed Ronald J. Darling Date 5-19-74 Authorized representative																																					