

WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

32667

1 LOCATION OF WATER WELL: County: Stafford		Fraction $\frac{1}{4}$ SE $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$	Section Number 26	Township No. T 25 S	Range Number R 13 ☐ E ☒ W
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ 10 1/2 south & 1 1/2 east of St. John, Ks.			Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m		
2 WATER WELL OWNER: Wade Harrison RR#, Street Address, Box #: 156 SE 90th. St. City, State, ZIP Code : St. John, Ks. 67576					
3 LOCATE WELL WITH AN "X" IN SECTION BOX: 		4 DEPTH OF COMPLETED WELL 121 ft. Depth(s) Groundwater Encountered (1)..... ft. (2)..... ft. (3)..... ft. WELL'S STATIC WATER LEVEL 13 1/2 ft. below land surface measured on mo/day/yr. 1-8-09 Pump test data: Well water was 36 1/2 ft. after 2 hours pumping 958 gpm EST. YIELD 1260 gpm. Well water was 40 1/2 ft. after 3 hours pumping 1260 gpm Bore Hole Diameter 30 in. to 121 ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted..... Water well disinfected? ☒ Yes ☐ No			
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 41 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 18 in., Weight Sch 40 lbs./ft., Wall thickness or gauge No. TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☒ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☐ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 121 ft. to 41 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 121 ft. to 20 ft., From ft. to ft. From ft. to ft., From ft. to ft.					
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From ft. to ft., From ft. to ft., From 20 ft. to 0 ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☐ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well None Direction from well Distance from well					
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS
0	5	Fine sand	113	116	Hard clay
5	33	Clay & fine sand	116	121	Sand & gravel-coarse/medium
33	84	Sand & gravel			
84	91	Sandy clay			
91	100	Sand & gravel			
100	106	Clay w/some gravel			
106	107	Hard Streak			
107	111	Clay w/some sand			
111	112	Hard streak			
112	113	Clay w/some sand			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 6-1-09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/year) 6-10-09 under the business name of Rosencrantz-Bemis by (signature) <i>[Signature]</i>					
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .					