

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD  
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment  
(Water well Contractors)  
Topeka, Kansas 66620

1. Location of well: County <b>Stafford</b>		Fraction <b>1/4 1/4 CSW/4</b>		Section number <b>8</b>		Township number <b>T 25 S R 13 NW</b>		Range number	
2. Distance and direction from nearest town or city: <b>7 S 13 1/4 W</b>				3. Owner of well: <b>Curtis O'Dell</b>					
Street address of well location if in city: <b>St. John, KS</b>				R.R. or street:					
				City, state, zip code: <b>R2 St. John, KS</b>					
4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. <b>30</b> in. Completion date <b>1-17-76</b>					
				Well depth <b>118</b> ft.					
				7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary					
5. Type and color of material				From		To		8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other	
Top Soil - Sandy Clay				0		55		9. Casing: Material <b>IRON</b> Height: <input checked="" type="checkbox"/> Above or below	
Sand - Gravel				55		75		Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <b>24</b> in.	
Sand - Clay Strks				75		85		RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight _____ lbs./ft.	
Gravel				85		98		Dia. <b>16</b> in. to <b>88</b> ft. depth Wall Thickness: inches or	
Clay				98		101		Dia. _____ in. to _____ ft. depth Gage No. <b>314</b>	
Sand - Gravel				101		118		10. Screen: Manufacturer's name <b>Daerr</b>	
								Type <b>IRON</b> Dia. <b>16"</b>	
								Slot/gauze <b>1/8</b> Length <b>30'</b>	
								Set between <b>88</b> ft. and <b>118</b> ft.	
								Gravel pack? <input checked="" type="checkbox"/> Size range of material <b>1/4-3/4"</b>	
								11. Static water level: _____ mo./day/yr.	
								<b>16</b> ft. below land surface Date <b>1-17-76</b>	
								12. Pumping level below land surfaces:	
								<b>53</b> ft. after <b>4</b> hrs. pumping <b>1100</b> g.p.m.	
								_____ ft. after _____ hrs. pumping _____ g.p.m.	
								Estimated maximum yield <b>1400</b> g.p.m.	
								13. Water sample submitted: _____ mo./day/yr.	
								Yes <input checked="" type="checkbox"/> No <input type="checkbox"/> Date _____	
								14. Well head completion:	
								<input type="checkbox"/> Pitless adapter <b>24</b> Inches above grade	
								15. Well grouted? <input checked="" type="checkbox"/>	
								With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete	
								Depth: From <b>0</b> ft. to <b>10</b> ft.	
								16. Nearest source of possible contamination: <b>None</b>	
								ft. _____ Direction _____ Type _____	
								Well disinfected upon completion? _____ Yes _____ No	
								17. Pump:	
								Not installed	
								Manufacturer's name <b>Boulds</b>	
								Model number <b>4125MD</b> HP <b>30</b> Volts _____	
								Length of drop pipe <b>80</b> ft. capacity <b>1000</b> g.p.m.	
								Type:	
								<input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine	
								<input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating	
								<input type="checkbox"/> Centrifugal <input type="checkbox"/> Other	
(Use a second sheet if needed)									
18. Elevation:		19. Remarks:		20. Water well contractor's certification:					
Topography:				This well was drilled under my jurisdiction and this report					
<input type="checkbox"/> Hill				is true to the best of my knowledge and belief.					
<input type="checkbox"/> Slope				<b>Kelly's Water Well Ser 186</b>					
<input checked="" type="checkbox"/> Upland				Business name <b>R2 Great Bend, KS</b> License No. _____					
<input type="checkbox"/> Valley				Address _____					
				Signed <b>Kelly Price</b> Date <b>1-20-76</b>					
				Authorized representative					

T 25 S R 13 NW  
 Sec 8  
 1/4 CSW