


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County STAFFORD	Fraction NE 1/4 SW 1/4 NW 1/4	Section number 14	Township number T 25 S	Range number R 13 W ERM
2. Distance and direction from nearest town or city: Street address of well location if in city:		8.5 E OF ST. JOHN, KS		3. Owner of well: LLOYD ESTES R.R. or street: City, state, zip code: ST. JOHN, KS		
4. Locate with "X" in section below: N W E S 1 Mile		Sketch map: 		6. Bore hole dia. 30 in. Completion date 26 MAR 77 Well depth 92 ft.		
5. Type and color of material		From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
SOIL		0	4	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other		
CLAY, BLUE		4	6	9. Casing: Material STL Height Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight ☐ lbs./ft. Dia. 1 1/2 in. to 52 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 188		
CLAY, SANDY GREEN		6	21	10. Screen: Manufacturer's name W A BROWN Type PROFLO Dia. 1 1/2 in. Slot/gauze 1/8 Length 40' Set between 52 ft. and 92 ft. Gravel pack? Yes Size range of material 1/4 - 1/2		
SAND, FINE W/ GREEN CLAY		21	31	11. Static water level: 14 ft. below land surface Date 23 MAR 77 mo./day/yr.		
SAND, COARSE & MED TO COARSE GRAVEL		31	60	12. Pumping level below land surfaces: 39 ft. after 2 hrs. pumping 901 g.p.m. 48 ft. after 1/2 hrs. pumping 1280 g.p.m. Estimated maximum yield ☐ g.p.m.		
SAND, CEMENTED		60	65	13. Water sample submitted: ☐ Yes ☒ No Date ☐		
SAND, COARSE & MED TO COARSE GRAVEL		65	82	14. Well head completion: ☐ Pitless adapter 12 inches above grade		
CLAY, WHITE		82	85	15. Well grouted? Yes With: ☐ Neat cement ☒ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.		
SAND, FINE TO COARSE & MED GRAVEL		85	91	16. Nearest source of possible contamination: NONE ft. Direction ☐ Type ☐ Well disinfected upon completion? ☒ Yes ☐ No		
SAND, FINE TO COARSE W/ CLAY		91	104	17. Pump: ☐ Not installed Manufacturer's name Flowm Model number ☐ HP 60 Volts ☐ Length of drop pipe 70 ft. capacity 800 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other		
SAND, FINE TO COARSE & MED GRAVEL		104	140	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. CENTRAL WELL & PUMP 325 Business name License No. Address 1219 TAYLOR PRATT Signed J. Honanichl Date 26 MAR 77 Authorized representative		
SHALE, RED		140	150			
18. Elevation:		19. Remarks: CONCRETE PAD POURED AT SURFACE BY OWNER				
Topography: ☐ Hill ☐ Slope ☒ Upland ☐ Valley						