

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: STAFFORD		NW 1/4 SE 1/4 SE 1/4	15	T 25 S	R 13 EW
Distance and direction from nearest town or city street address of well if located within city? 6W 6S OF STAFFORD, KS					
2 WATER WELL OWNER:		Board of Agriculture, Division of Water Resources			
RR#, St. Address, Box # :		Application Number:			
City, State, ZIP Code :		Stafford, Kansas 67578			
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL: 90 ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. 20 ft. 2. ft. 3. ft.			
		WELL'S STATIC WATER LEVEL 18.5 ft. below land surface measured on mo/day/yr MAR 25 81			
		Pump test data: Well water was 30.5 ft. after 1 hours pumping 800 gpm			
		Est. Yield 1300 gpm: Well water was 34.5 ft. after 1 hours pumping 1000 gpm			
		Bore Hole Diameter 30 in. to 90 ft., and in. to ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) ② Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well			
		Was a chemical/bacteriological sample submitted to Department? Yes.....No X; If yes, mo/day/yr sample was submitted			
		Water Well Disinfected? Yes X No			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued Clamped			
① Steel 3 RMP (SR)		Welded X			
2 PVC 4 ABS		Threaded			
Blank casing diameter 16 in. to 36 ft., Dia		Casing height above land surface 12 in., weight 32.7 lbs./ft. Wall thickness or gauge No. 188			
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
① Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify)		12 None used (open hole)			
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS					
SCREEN OR PERFORATION OPENINGS ARE:		5 Gauzed wrapped 8 Saw cut 11 None (open hole)			
1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes		10 Other (specify)			
2 Louvered shutter ④ Key punched 7 Torch cut					
SCREEN-PERFORATED INTERVALS:		From 36 ft. to 56 ft., From ft. to ft.			
		From 74 ft. to 90 ft., From ft. to ft.			
GRAVEL PACK INTERVALS:		From ft. to ft., From ft. to ft.			
		From 10 ft. to 90 ft., From ft. to ft.			
6 GROUT MATERIAL:		1 Neat cement 2 Cement grout ③ Bentonite 4 Other			
Grout Intervals: From 0 ft. to 10 ft., From ft. to ft.					
What is the nearest source of possible contamination:		10 Livestock pens 14 Abandoned water well			
1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well		12 Fertilizer storage 16 Other (specify below)			
2 Sewer lines 5 Cess pool 8 Sewage lagoon 13 Insecticide storage NONE					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard					
Direction from well?		How many feet?			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHOLOGIC LOG
0	2	Sandy soil			
2	11	Clay, blue			
11	20	Clay, gray and white			
20	30	Sand, fine to coarse			
30	56	Sand, fine to coarse and fine to coarse gravel, loose			
56	75	Clay, tan and white			
75	90	Sand, fine to coarse and fine to med gravel, loose			
90	96	Clay, tan			
96	110	Sand, very fine to coarse, loose			
110	138	Sand, fine to coarse and fine to coarse gravel			
138	150	Shale, blue			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ① constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) MAY 22 81 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 325 This Water Well Record was completed on (mo/day/yr) JUNE 28 81 under the business name of Central Well & Pump Inc. Pratt, Kansas by (signature) Philonomich					
INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.					