

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction 1/4 1/4 SE 1/4	Section number 22	Township number T 25 S	Range number R 13 E																																										
2. Distance and direction from nearest town or city: 10 miles SE of St. John, KS Street address of well location if in city:				3. Owner of well: Ray Harrison R.R. or street: Route 2 City, state, zip code: St. John, KS 67576																																												
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile Sketch map:				6. Bore hole dia. 24 in. Completion date 6-18-79 Well depth 130 ft. Pump Set 6-20-79																																												
5. Type and color of material. <table border="1"><thead><tr><th></th><th>From</th><th>To</th></tr></thead><tbody><tr><td>Top Soil</td><td>0</td><td>8</td></tr><tr><td>Brown Clay</td><td>8</td><td>16</td></tr><tr><td>Sandy clay</td><td>16</td><td>21</td></tr><tr><td>Fine Sand</td><td>21</td><td>28</td></tr><tr><td>Sandy Clay</td><td>28</td><td>30</td></tr><tr><td>Sand & Gravel</td><td>30</td><td>37</td></tr><tr><td>Clay, Hard & Yellow</td><td>37</td><td>42</td></tr><tr><td>Sand & Gravel</td><td>42</td><td>60</td></tr><tr><td>Hard Brown Clay</td><td>60</td><td>76</td></tr><tr><td>Fine Sand</td><td>76</td><td>85</td></tr><tr><td>Sand & Gravel</td><td>85</td><td>125</td></tr><tr><td>Brown Clay</td><td>125</td><td>129</td></tr><tr><td>Sand & Gravel</td><td>129</td><td>130</td></tr></tbody></table>					From	To	Top Soil	0	8	Brown Clay	8	16	Sandy clay	16	21	Fine Sand	21	28	Sandy Clay	28	30	Sand & Gravel	30	37	Clay, Hard & Yellow	37	42	Sand & Gravel	42	60	Hard Brown Clay	60	76	Fine Sand	76	85	Sand & Gravel	85	125	Brown Clay	125	129	Sand & Gravel	129	130	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary		
					From	To																																										
				Top Soil	0	8																																										
				Brown Clay	8	16																																										
				Sandy clay	16	21																																										
				Fine Sand	21	28																																										
				Sandy Clay	28	30																																										
				Sand & Gravel	30	37																																										
				Clay, Hard & Yellow	37	42																																										
				Sand & Gravel	42	60																																										
Hard Brown Clay	60	76																																														
Fine Sand	76	85																																														
Sand & Gravel	85	125																																														
Brown Clay	125	129																																														
Sand & Gravel	129	130																																														
8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other																																																
9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>90</u> ft. depth Wall Thickness: inches or Dia. <u> </u> in. to <u> </u> ft. depth gage No. <u>7 ga.</u>																																																
10. Screen: Manufacturer's name <u>Doerr</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot gauze <u>1/8"</u> Length <u>40'</u> Set between <u>90</u> ft. and <u>130</u> ft. <u> </u> ft. and <u> </u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8-200</u>																																																
11. Static water level: <u>22</u> ft. below land surface Date <u>6-18-79</u> mo./day/yr.																																																
12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.																																																
13. Water sample submitted: <u> </u> mo./day/yr. <u> </u> Yes ☒ No ☐ Date <u> </u>																																																
14. Well head completion: <u> </u> Pitless adapter <u>12</u> inches above grade																																																
15. Well grouted? <u>Yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.																																																
16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No ☐																																																
17. Pump: <u> </u> Not installed Manufacturer's name <u>Peerless Pump Co.</u> Model number <u>12LB-3</u> HP <u>80</u> Volts <u> </u> Length of drop pipe <u>70</u> ft. capacity <u>1000</u> g.p.m. Type: <u> </u> Submersible ☒ Turbine <u> </u> Jet <u> </u> Reciprocating <u> </u> Centrifugal <u> </u> Other																																																
(Use a second sheet if needed)																																																
18. Elevation: Topography: <u> </u> Hill <u> </u> Slope <u> </u> Upland <u> </u> Valley		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. <u> </u> Address <u>Rt 1, Great Bend, KS 67530</u> Signed <u>DW Clarke</u> Date <u>6/22/79</u> Authorized representative																																												

25
13
3
2
2
1/4
center of SE