

County Stafford		Fraction 1/4 1/4 CNE 1/4	Section number 29	Township number T 25 S	Range number R 13 EW
---------------------------	--	----------------------------------	-----------------------------	---------------------------------	-------------------------------

2. Distance and direction from nearest town or city: 9 1/2 mi. South of St. John, KS. Street address of well location if in city:		3. Owner of well: Lee Curtis R.R. or street: Box 163 City, state, zip code: St. John, KS 67576	
--	--	---	--

4. Locate with "X" in section below:		Sketch map:	
--------------------------------------	--	-------------	--

5. Type and color of material	From	To
Top soil	0	4
Brown & gray clay & limestone	4	28
Sand & Gravel	28	58
Brown clay	58	59
Sand & gravel	59	67
Brown & gray clay & gravel streaks	67	80
Sand & gravel	80	90

6. Bore hole dia. <u>24</u> in. Completion date <u>4-19-76</u> Well depth <u>90</u> ft.	
7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
8. Use: Domestic ☐ Public supply ☐ Industry ☐ ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
9. Casing: Material <u>Steel</u> Height: Above or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>40</u> ft. depth Wall Thickness: inches or Dia. <u>16</u> in. to <u>80</u> ft. depth gage No. <u>7 ga.</u>	
10. Screen: Manufacturer's name <u>W. A. Brown</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot/gauze <u>8 1/8</u> Length <u>40'</u> Set between <u>40</u> ft. and <u>70</u> ft. <u>80</u> ft. and <u>90</u> ft. Gravel pack? ☒ Size range of material <u>3/8-200</u>	
11. Static water level: _____ mo./day/yr. <u>13' 8"</u> ft. below land surface Date <u>4-15-76</u>	
12. Pumping level below land surfaces: N/C _____ ft. after _____ hrs. pumping _____ g.p.m. _____ ft. after _____ hrs. pumping _____ g.p.m. Estimated maximum yield _____ g.p.m.	
13. Water sample submitted: _____ mo./day/yr. Yes ☒ No ☐ Date _____	
14. Well head completion: ☐ Pitless adapter <u>12</u> Inches above grade	
15. Well grouted? <u>Yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
16. Nearest source of possible contamination: ft. _____ Direction _____ Type _____ Well disinfected upon completion? Yes ☐ No ☒	
17. Pump: Manufacturer's name <u>FMC Corp/Peerless</u> Model number <u>12LB-2</u> HP <u>60</u> Volts _____ Length of drop pipe <u>60</u> ft. capacity <u>900</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	

(Use a second sheet if needed)	
--------------------------------	--

18. Elevation:	19. Remarks:	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq. Inc. <u>185</u> Business name License No. _____ Address <u>Great Bend, KS 67530</u> Signed _____ Date <u>4-22-</u> Authorized representative
----------------	--------------	--