

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 093 STAFFORD SW 1/4 SW 1/4 NW 1/4 23 T 25 S R 14 W

Distance and direction from nearest town or city street address of well if located within city?

6 S. 7 1/2 E, OF MACKSVILLE, KS

2 WATER WELL OWNER: SUITER, DON 016
 RR#, St. Address, Box #: Board of Agriculture, Division of Water Resources

City, State, ZIP code : MACKSVILLE, KS 67557- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10
1	2	3	4	5	6	7	8	9	10

4 DEPTH OF COMPLETED WELL 80 ELEVATION:
 Depth(s) Groundwater Encountered 1. 35 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 35 ft. below land surface measured on mo/day/yr 7 /31/90
 Pump testdata: Well water was ft. after hours pumping gpm
 Estimated Yield 25 gpm: Well water was ft. after hours pumping gpm
 Bore Hole Diameter 8.75 in. to 80 ft., and in. to ft.
 WELL WATER TO BE USED AS: 01 DOMESTIC
 Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 60 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 80 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 80 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From 1 ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: CATTLE PASTURE
 Direction from well? ALLL How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	21	TAN CLAY			
21	29	05 SAND AND CLAY			
29	34	TAN CLAY			
34	47	05 SAND AND 17 GRAVEL			
47	53	TAN CLAY			
53	80	05 SAND AND COURSE			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 7 /28/90 and this record is true to the best of my knowledge and belief. Kansas
 Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 09/19/91
 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse