


1 LOCATION OF WATER WELL: Fraction <u>SE 1/4 SE 1/4 SE 1/4</u> Section Number <u>2</u> Township Number <u>T 25 S</u> Range Number <u>R 15 E</u>					
County: <u>Stafford</u> Distance and direction from nearest town or city street address of well if located within city? <u>3/4 South of Wicksville west into</u>					
2 WATER WELL OWNER: <u>Myron G. Hamm</u> Board of Agriculture, Division of Water Resources Application Number: <u>TCKLE P6 57444346</u>					
RR#, St. Address, Box # : <u>1342 CR10</u> City, State, ZIP Code : <u>Gunnison, CO 81230-74</u>					
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 					
4 DEPTH OF COMPLETED WELL <u>74</u> ft. ELEVATION: <u>9-20-06</u> Depth(s) Groundwater Encountered <u>28</u> ft. 2 <u>8</u> ft. 3 <u>9-20-06</u> WELL'S STATIC WATER LEVEL <u>28</u> ft. below land surface measured on mo/day/yr Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm Est. Yield _____ gpm: Well water was _____ ft. after _____ hours pumping _____ gpm WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well ☒ 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below) ☐ 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Was a chemical/bacteriological sample submitted to Department? Yes _____ No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes ☒ No					
5 TYPE OF BLANK CASING USED: 1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped _____ ☒ 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded _____ Blank casing diameter <u>5</u> in. to <u>74</u> ft., Dia _____ in. to _____ ft., Dia _____ in. to _____ ft. Casing height above land surface <u>12</u> in., weight <u>160</u> lbs./ft. Wall thickness or gauge No. _____ TYPE OF SCREEN OR PERFORATION MATERIAL: ☒ PVC 10 Asbestos-Cement 1 Steel 3 Stainless Steel 5 Fiberglass 8 RMP (SR) 11 Other (Specify) _____ 2 Brass 4 Galvanized Steel 6 Concrete tile 9 ABS 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 1 Continuous slot ☒ 3 Mill slot 6 Wire wrapped 9 Drilled holes 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) _____ ft. SCREEN-PERFORATED INTERVALS: From <u>74</u> ft. to <u>54</u> ft., From _____ ft. to _____ ft. GRAVEL PACK INTERVALS: From <u>74</u> ft. to <u>24</u> ft., From _____ ft. to _____ ft. From _____ ft. to _____ ft., From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout ☒ 3 Bentonite 4 Other _____ Grout Intervals: From <u>24</u> ft. to <u>0</u> ft., From _____ ft. to _____ ft., From _____ ft. to _____ ft. What is the nearest source of possible contamination: ☒ 10 Livestock pens 14 Abandoned water well ☒ 1 Septic tank 4 Lateral lines 7 Pit privy 11 Fuel storage 15 Oil well/Gas well ☒ 2 Sewer lines 5 Cess pool 8 Sewage lagoon 12 Fertilizer storage 16 Other (specify below) 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 13 Insecticide storage Direction from well? <u>West SW</u> How many feet? <u>150ft+</u>					
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Sandy Top Soil			
2	16	BLACK Clay			
16	28	Tan Sand			
28	35	Tan Clay			
35	40	Brown Clay			
40	70	Fine Sand			
70	74	Coarse Sand & Gravel - 5mm 11			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>9-20-06</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's Licence No. <u>672</u> This Water Well Record was completed on (mo/day/yr) <u>9-20-06</u> under the business name of <u>CROW IS</u> by (signature) 