


USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

1. Location of well:		County Stafford	Fraction CENTER OF 1/4 1/4 1/4	Section number 20	Township number T 25 S R 15 E W	Range number
2. Distance and direction from nearest town or city: 21 miles Southwest of St. John, KS Street address of well location if in city:			3. Owner of well: F. Bryce Lamb R.R. or street: Rural Route City, state, zip code: Macksville, KS 67557			
4. Locate with "X" in section below: N 1 Mile W E S 1 Mile 			Sketch map: 6. Bore hole dia. 24 in. Completion date 8-8-77 Well depth 140 ft.			
5. Type and color of material			From	To	7. ☐ Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary	
Sandy top soil			0	4	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other	
Clay			4	16	9. Casing: Material steel Height Above or below Threaded ☐ Welded ☒ Surface 12 in. RMP ☐ PVC ☐ Weight 30.3 lbs./ft. Dia. 16 in. to 80 ft. depth Wall Thickness: inches or Dia. ☐ in. to ☐ ft. depth gage No. 7 ga.	
Soft sandstone & clay			16	19	10. Screen: Manufacturer's name W. A. Brown Type Double-slot Dia. 16" Slot gauge 1/8 Length 60' Set between 80 ft. and 140 ft. ft. and ☐ ft. Gravel pack? yes Size range of material 3/8-200	
Fine sand & gravel			19	23	11. Static water level: ☐ mo./day/yr. 13 ft. below land surface Date 7-27-77	
Clay			23	29	12. Pumping level below land surfaces: N/C ☐ ft. after ☐ hrs. pumping ☐ g.p.m. ☐ ft. after ☐ hrs. pumping ☐ g.p.m. Estimated maximum yield ☐ g.p.m.	
Clay & broken limestone streaks			29	42	13. Water sample submitted: ☐ mo./day/yr. ☐ Yes ☒ No Date ☐	
Sand & gravel			42	45	14. Well head completion: ☐ Pitless adapter 12 Inches above grade	
Clay			45	49	15. Well grouted? yes With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From 0 ft. to 10 ft.	
Sand & gravel & clay streak			49	69	16. Nearest source of possible contamination: Field ft. ☐ Direction ☐ Type ☐ Well disinfected upon completion? ☐ Yes ☒ No	
Clay			69	83	17. Pump: ☐ Not installed Manufacturer's name Peerless Pump Model number 12LB-3 HP 80 Volts --- Length of drop pipe 60 ft. capacity 900 g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
Sand & gravel & clay streaks at 104' & 115' to			83	140	20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name License No. Address Great Bend, KS 67530 Signed [Signature] Date 8-9-77 Authorized representative	
120'						
(Use a second sheet if needed)						
18. Elevation:		19. Remarks:				
Topography: ☐ Hill ☐ Slope ☐ Upland ☐ Valley						

25
150
20
C
1/4 1/4 1/4