

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 093 STAFFORD NE 1/4 SE 1/4 NW 1/4 26 T 25 S R 15 W

Distance and direction from nearest town or city street address of well if located within city?

7 1/2S. 1 1/2E. OF MACKSVILLE, KANS.

2 WATER WELL OWNER: SUITER, DON 024
 RR#, St. Address, Box #: Board of Agriculture, Division of Water Resources
 City, State, ZIP code : MACKSVILLE, KS 67557- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NW	X	NE
2	SW		SE

4 DEPTH OF COMPLETED WELL 60 ELEVATION:
 Depth(s) Groundwater Encountered 1. 10 ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 10 ft. below land surface measured on mo/day/yr 7 /18/90
 Pump test data: Well water was ft. after hours pumping gpm

Estimated Yield gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter 8.75 in. to 60 ft., and in. to ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 40 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 40 ft. to 60 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 60 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: CATTLE PASTURE
 Direction from well? ALL How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	1	SILT & SAND			
1	8	TAN CLAY			
8	10	BLACK CLAY			
10	12	05 SAND			
12	28	BROWN CLAY			
28	40	05 SAND AND 17 GRAVEL			
40	42	BROWN CLAY			
42	60	17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 7 /18/90 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 07/07/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse