

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
 COUNTY: 093 STAFFORD NW 1/4 NW 1/4 SW 1/4 26 T 25 S R 15 W

Distance and direction from nearest town or city street address of well if located within city?

7 1/2 S, 1 E. OF MACKSVILLE, KS.

2 WATER WELL OWNER: JONES, JACK 104
 RR#, St. Address, Box #: 501 S. PINE Board of Agriculture, Division of Water Resources

City, State, ZIP code : PRATT, KS 67124- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

/ \				
1	NW		NE	
M				
i	W	X		E
l				
e	SW		SE	
\ /				

4 DEPTH OF COMPLETED WELL 96 ELEVATION:
 Depth(s) Groundwater Encountered 1. ft. 2. ft. 3. ft.

WELL'S STATIC WATER LEVEL 29 ft. below land surface measured on mo/day/yr
 Pump test data: Well water was ft. after hours pumping gpm

Estimated Yield gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter 8.75 in. to 96 ft., and in. to ft.

WELL WATER TO BE USED AS: 01 DOMESTIC

Was a chemical/bacteriological sample submitted to department? No ;
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
 Blank casing diameter 5 in. to 86 ft., Dia in. to ft., Dia in. to ft.
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 86 ft. to 96 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 25 ft. to 96 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
 Grout Intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination: CATTLE PASTURE
 Direction from well? ALL How many feet? 3

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	9	SILT & SAND			
9	38	TAN CLAY			
38	55	05 SAND AND 17 GRAVEL			
55	63	TAN CLAY			
63	96	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/2 /91 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 12/17/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse