

USE TYPEWRITER OR BALL
POINT PEN-PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

X Location of well:	County <u>Stafford</u>	Fraction <u>1/4 NW 1/4 SW 1/4</u>	Section number <u>36</u>	Township number <u>25</u>	Range number <u>15</u>
2. Distance and direction from nearest town or city: <u>8 mi So. & 2 East</u> <u>10 miles southeast</u> of <u>Macksville, KS</u> Street address of well location if in city:			3. Owner of well: <u>Fred Grunder</u> R.R. or street: <u>(?)</u> City, state, zip code: <u>St. John, KS 67576</u>		
4. Locate with "X" in section below:			Sketch map:		
5. Type and color of material			From	To	6. Bore hole dia. <u>24</u> in. Completion date <u>3-22-78</u> Well depth <u>100</u> ft. Pump Set <u>8-15-78</u>
Top soil			0	4	7. Cable tool ☐ Rotary ☐ Driven ☐ Dug ☐ Hollow rod ☐ Jetted ☐ Bored ☒ Reverse rotary
Gray clay			4	11	8. Use: ☐ Domestic ☐ Public supply ☐ Industry ☒ Irrigation ☐ Air conditioning ☐ Stock ☐ Lawn ☐ Oil field water ☐ Other
Sand & gravel & clay streak at 22'			11	32	9. Casing: Material <u>Steel</u> Height: <u>Above</u> or below Threaded ☐ Welded ☒ Surface <u>12</u> in. RMP ☐ PVC ☐ Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>23</u> ft. depth Wall Thickness: inches or Dia. <u>16</u> in. to <u>60</u> ft. depth gage No. <u>7</u> ga.
Brown clay			32	36	10. Screen: Manufacturer's name <u>W. A. Brown</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot gauze <u>1/8"</u> Length <u>60'</u> Set between <u>23</u> ft. and <u>43</u> ft. <u>60</u> ft. and <u>100</u> ft. Gravel pack? <u>Yes</u> Size range of material <u>3/8-200</u>
Sand & gravel & thin clay streaks			36	55	11. Static water level: <u>14</u> ft. below land surface Date <u>3-22-78</u>
Yellow clay			55	63	12. Pumping level below land surfaces: <u>Not Checked</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m.
Sand & gravel			63	99	13. Water sample submitted: <u> </u> mo./day/yr. Yes ☐ No ☒ Date <u> </u>
Sand & clay streaks			99	100	14. Well head completion: ☐ Pitless adapter <u>12</u> Inches above grade
(Use a second sheet if needed)			100	15. Well grouted? <u>Yes</u> With: ☒ Neat cement ☐ Bentonite ☐ Concrete Depth: From <u>0</u> ft. to <u>10</u> ft.	
(Use a second sheet if needed)			100	16. Nearest source of possible contamination: <u>FIELD</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <u> </u> Yes ☒ No	
(Use a second sheet if needed)			100	17. Pump: <u> </u> Not installed Manufacturer's name <u>Western Land Roller</u> Model number <u>4 12C H</u> HP <u>50</u> Volts <u> </u> Length of drop pipe <u>40</u> ft. capacity <u>1000</u> g.p.m. Type: ☐ Submersible ☒ Turbine ☐ Jet ☐ Reciprocating ☐ Centrifugal ☐ Other	
18. Elevation:	19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. <u>Clarke Well & Eq., Inc.</u> 185 Business name License No. <u> </u> Address <u>Great Bend, KS 67530</u> Signed <u>D. W. Clark</u> Date <u>8-15-78</u> Authorized representative		