

USE TYPEWRITER OR BALL POINT PEN-PRESS FIRMLY, PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and Environment-Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

| | | | | | | |
|--|--|--------------------------|---------------------------|--|--------------------------------|---------------------------|
| 1. Location of well: | | County Edwards | Fraction 1/4 1/4 CSW/4 | Section number 12 | Township number T 25 S R 16 | Range number EW |
| 2. Distance and direction from nearest town or city: 8 miles Southeast of Belpre, KS Street address of well location if in city: | | | | 3. Owner of well: Wayne Miller R.R. or street: Rural Route City, state, zip code: Macksville, KS 67557 | | |
| 4. Locate with "X" in section below: | | Sketch map: | | 6. Bore hole dia. <u>24</u> in. Completion date <u>4-12-77</u> Well depth <u>138</u> ft. | | |
| | | | | 7. <input type="checkbox"/> Cable tool <input type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input checked="" type="checkbox"/> Reverse rotary | | |
| | | | | 8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other | | |
| 5. Type and color of material | | From | To | 9. Casing: Material <u>steel</u> Height: <u>Above</u> or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface <u>12</u> in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <u>30.3</u> lbs./ft. Dia. <u>16</u> in. to <u>68</u> ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. <u>7 ga.</u> | | |
| Sand | | 0 | 11 | 10. Screen: Manufacturer's name <u>Doerr Metal</u> Type <u>Double-slot</u> Dia. <u>16"</u> Slot/gauze <u>1/8</u> Length <u>70'</u> Set between <u>68</u> ft. and <u>138</u> ft. <u>68</u> ft. and <u> </u> ft. Gravel pack? <u>yes</u> Size range of material <u>3/8-200</u> | | |
| Sandy clay & soft clay & sand | | 11 | 61 | 11. Static water level: <u> </u> mo./day/yr. <u>25' 6"</u> ft. below land surface Date <u>4-4-77</u> | | |
| Sand & gravel | | 61 | 66 | 12. Pumping level below land surfaces: <u>N/C</u> <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. <u> </u> ft. after <u> </u> hrs. pumping <u> </u> g.p.m. Estimated maximum yield <u> </u> g.p.m. | | |
| Clay | | 66 | 68 | 13. Water sample submitted: <u> </u> mo./day/yr. Yes <input type="checkbox"/> No <input checked="" type="checkbox"/> Date <u> </u> | | |
| Very course gravel | | 68 | 95 | 14. Well head completion: <input type="checkbox"/> Pitless adapter <u>12</u> Inches above grade | | |
| Yellow clay | | 95 | 97 | 15. Well grouted? <u>yes</u> With: <input checked="" type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input type="checkbox"/> Concrete Depth: From <u>0</u> ft. to <u>10</u> ft. | | |
| Sand & gravel & thin clay streaks | | 97 | 136 | 16. Nearest source of possible contamination: <u>Field</u> ft. <u> </u> Direction <u> </u> Type <u> </u> Well disinfected upon completion? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | |
| Sandy clay | | 136 | 138 | 17. Pump: <input type="checkbox"/> Not installed Manufacturer's name <u>Peerless Pump</u> Model number <u>12LB-3</u> HP <u>80</u> Volts <u> </u> Length of drop pipe <u>70</u> ft. capacity <u>900</u> g.p.m. Type: <input type="checkbox"/> Submersible <input checked="" type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other | | |
| (Use a second sheet if needed) | | | | 20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Clarke Well & Eq., Inc. 185 Business name <u> </u> License No. <u> </u> Address <u>Great Bend, KS 67530</u> Signed <u> </u> Date <u>4-21-77</u> Authorized representative | | |
| 18. Elevation: | | 19. Remarks: | | | | |
| Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input type="checkbox"/> Upland <input type="checkbox"/> Valley | | | | | | |

25
 16
 W
 12
 CSW
 1/4
 1/4
 1/4
 1/4
 Sec

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5