

USE TYPEWRITER OR BALL
POINT PEN—PRESS FIRMLY,
PRINT CLEARLY.

WATER WELL RECORD
KSA 82a-1201-1215

Kansas Department of Health and
Environment—Division of Environment
(Water well Contractors)
Topeka, Kansas 66620

X Location of well:		County Edwards	Fraction 5 1/2 1/4 1/4 1/4	Section number 34	Township number 26	Range number 15
X 2. Distance and direction from nearest town or city: 1/2 mi. E of			3. Owner of well: Walter Gibson			
Street address of well location if in city: Trussdale			R.R. or street: City, state, zip code: Trussdale, Ks.			
X 4. Locate with "X" in section below:		Sketch map:		6. Bore hole dia. 29 in. Completion date 7-30-74 Well depth 91 ft. 12		
				7. Cable tool <input checked="" type="checkbox"/> Rotary <input type="checkbox"/> Driven <input type="checkbox"/> Dug <input type="checkbox"/> Hollow rod <input type="checkbox"/> Jetted <input type="checkbox"/> Bored <input type="checkbox"/> Reverse rotary		
5. Type and color of material		From	To	8. Use: <input type="checkbox"/> Domestic <input type="checkbox"/> Public supply <input type="checkbox"/> Industry <input checked="" type="checkbox"/> Irrigation <input type="checkbox"/> Air conditioning <input type="checkbox"/> Stock <input type="checkbox"/> Lawn <input type="checkbox"/> Oil field water <input type="checkbox"/> Other		
Top Soil Sandy		0	2	9. Casing: Material steel Height: Above or below Threaded <input type="checkbox"/> Welded <input checked="" type="checkbox"/> Surface 18 in. RMP <input type="checkbox"/> PVC <input type="checkbox"/> Weight <input type="checkbox"/> lbs./ft. Dia. 16 in. to 91 ft. depth Wall Thickness: inches or Dia. <input type="checkbox"/> in. to <input type="checkbox"/> ft. depth gage No. 7		
Brown Clay		2	4 1/2	10. Screen: Manufacturer's name Doerrs Type steel Dia. 16 Slot gauge 3/16 Length 40 Set between 51 ft. and 91 ft. ft. and <input type="checkbox"/> ft. Gravel pack? <input checked="" type="checkbox"/> Size range of material 1/2 3/4 3/8		
Sand & Gravel loose		4 1/2	15	11. Static water level: <input type="checkbox"/> mo./day/yr. 6 ft. below land surface Date 7-24-74		
Gray Clay		15	21	12. Pumping level below land surfaces: 7 ft. after 1 hrs. pumping 1400 g.p.m. <input type="checkbox"/> ft. after <input type="checkbox"/> hrs. pumping <input type="checkbox"/> g.p.m. Estimated maximum yield 1600 g.p.m.		
Fine Sand & Clay		21	23	13. Water sample submitted: <input type="checkbox"/> mo./day/yr. <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Date 7-30-74		
Sand & Gravel Clear Coarse loose		23	56	14. Well head completion: <input type="checkbox"/> Pitless adapter <input type="checkbox"/> Inches above grade		
Brown Clay		56	65 1/2	15. Well grouted? <input checked="" type="checkbox"/> With: <input type="checkbox"/> Neat cement <input type="checkbox"/> Bentonite <input checked="" type="checkbox"/> Concrete Depth: From 0 ft. to 10 ft.		
Sand & Gravel Clear Coarse loose		65 1/2	91	16. Nearest source of possible contamination: ft. 4 m Direction W Type SEPTIC Well disinfected upon completion? <input type="checkbox"/> Yes <input type="checkbox"/> No		
Brown Clay		91	92	17. Pump: <input checked="" type="checkbox"/> Not installed Manufacturer's name <input type="checkbox"/> Model number <input type="checkbox"/> HP <input type="checkbox"/> Volts <input type="checkbox"/> Length of drop pipe <input type="checkbox"/> ft. capacity <input type="checkbox"/> g.p.m. Type: <input type="checkbox"/> Submersible <input type="checkbox"/> Turbine <input type="checkbox"/> Jet <input type="checkbox"/> Reciprocating <input type="checkbox"/> Centrifugal <input type="checkbox"/> Other		
(Use a second sheet if needed)						
18. Elevation: 2058'		19. Remarks:		20. Water well contractor's certification: This well was drilled under my jurisdiction and this report is true to the best of my knowledge and belief. Rosenkrantz-Bemis 134 Business name License No. Address Great Bend, Ks. Signed Fredia Radon Date 9/29/74 Authorized representative		
Topography: <input type="checkbox"/> Hill <input type="checkbox"/> Slope <input checked="" type="checkbox"/> Upland <input type="checkbox"/> Valley						

Forward the white, blue and pink copies to the Department of Health and Environment

Form WWC-5