


1 LOCATION OF WATER WELL: Fraction $\frac{1}{4}$ C $\frac{1}{4}$ SW $\frac{1}{4}$ Section Number 21 Township Number T 25 S Range Number R 17 EAW
 County: Edwards

Distance and direction from nearest town or city street address of well if located within city? 2 3/4 N 1 W of Jellsburg

2 WATER WELL OWNER: Pat Platts
 RR#, St. Address, Box # :
 City, State, ZIP Code : Lewis, Ks. 67552
 Board of Agriculture, Division of Water Resources
 Application Number: 34,097

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

 4 DEPTH OF COMPLETED WELL: 124 ft. ELEVATION:
 Depth(s) Groundwater Encountered 1. 40 ft. 2. ft. 3. ft.
 WELL'S STATIC WATER LEVEL 40 ft. below land surface measured on mo/day/yr 3-24-81
 Pump test data: Well water was 55 ft. after 1 hours pumping 1200 gpm
 Est. Yield 1400 gpm: Well water was 65 ft. after 1 1/2 hours pumping 1400 gpm
 Bore Hole Diameter: 29 in. to 124 ft., and in. to ft.
 WELL WATER TO BE USED AS:
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)
 2 Irrigation 4 Industrial 7 Lawn and garden only 10 Observation well
 Was a chemical/bacteriological sample submitted to Department? Yes.....No.; If yes, mo/day/yr sample was submitted
 Water Well Disinfected? Yes HTH No

5 TYPE OF BLANK CASING USED:
 Steel 3 RMP (SR) 6 Asbestos-Cement 9 Other (specify below) Welded
 2 PVC 4 ABS 7 Fiberglass Threaded
 Blank casing diameter 16 in. to 80 ft., Dia. in. to ft., Dia. in. to ft.
 Casing height above land surface 18 in., weight lbs./ft. 7 Wall thickness or gauge No.
 TYPE OF SCREEN OR PERFORATION MATERIAL:
 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)
 SCREEN OR PERFORATION OPENINGS ARE:
 1 Continuous slot 3 Mill slot 6 Wire wrapped 9 Drilled holes
 2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify)
 5 Gauzed wrapped 8 Saw cut 11 None (open hole)
 SCREEN-PERFORATED INTERVALS: From 80 ft. to 124 ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 10 ft. to 125 ft., From ft. to ft.

6 GROUT MATERIAL: Neat cement 2 Cement grout 3 Bentonite 4 Other
 Grout Intervals: From 0 ft. to 10 ft., From ft. to ft., From ft. to ft.
 What is the nearest source of possible contamination:
 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)
 13 Insecticide storage
 Direction from well? South How many feet? 1/4 mile

| FROM | TO | LITHOLOGIC LOG | FROM | TO | LITHOLOGIC LOG |
|------|-----|-----------------------------|------|----|----------------|
| 0 | 5 | Sandy top soil | | | |
| 5 | 30 | Sandy brown clay | | | |
| 30 | 40 | Dirty brown sand and gravel | | | |
| 40 | 86 | Sand and gravel | | | |
| 86 | 87 | Brown clay | | | |
| 87 | 103 | Sand and gravel | | | |
| 103 | 110 | Clay w/ sand mixed | | | |
| 110 | 114 | Brown and white clay | | | |
| 114 | 124 | Sand and gravel | | | |
| 124 | 125 | Hard white rock | | | |

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was constructed, reconstructed, or plugged under my jurisdiction and was completed on (mo/day/year) 6-30-81 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 134 This Water Well Record was completed on (mo/day/yr) 7-24-81 under the business name of Rosencrantz-Bemis Ent. by (signature) Jora Dodson

INSTRUCTIONS: Use typewriter or ball point pen, PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Division of Environment, Environmental Geology Section, Topeka, KS 66620. Send one to WATER WELL OWNER and retain one for your records.

OFFICE USE ONLY
T 25
R
EN
SEC. 21
C 8514