

WATER WELL RECORD Form WWC-5 KSA B2a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
COUNTY: Edwards NW 1/4 SW 1/4 SW 1/4 24 T 25 S R 17 W

Distance and direction from nearest town or city street address of well if located within city?  
1 1/2 E, 2 1/4 N. OF FELLOSBURG, KS

2 WATER WELL OWNER: KENNY KEEN 183  
RR#, St. Address, Box #: R.1, BOX 68A Board of Agriculture, Division of Water Resources

City, State, ZIP code : LEWIS, KS 67552- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 80 ELEVATION:  
Depth(s) Groundwater Encountered 1. 21 ft. 2. ft. 3. ft.  
WELL'S STATIC WATER LEVEL 21 ft. below land surface measured on mo/day/yr  
Pump test data: Well water was ft. after hours pumping gpm  
Estimated Yield gpm: Well water was ft. after hours pumping gpm  
Bore Hole Diameter 8.75 in. to 80 ft., and in. to ft.  
WELL WATER TO BE USED AS: 01 DOMESTIC  
Was a chemical/bacteriological sample submitted to department? No ;  
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
Blank casing diameter 5 in. to 70 ft., Dia in. to ft., Dia in. to ft.  
Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26  
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 70 ft. to 80 ft., From ft. to ft.  
From ft. to ft., From ft. to ft.  
GRAVEL PACK INTERVALS: From 25 ft. to 80 ft., From ft. to ft.  
From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE  
Grout Intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.  
What is the nearest source of possible contamination: CATTLE PASTURE  
Direction from well? ALL How many feet? 3

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	19	TAN CLAY			
19	41	05 SAND AND 17 GRAVEL			
41	46	GREY CLAY			
46	80	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/12/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 11/30/92 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse