

1 LOCATION OF WATER WELL:	Fraction	Section Number	Township Number	Range Number
County: Edwards	NW 1/4 SW 1/4 NW 1/4	33	T 25 S	R 17 E (W)

Distance and direction from nearest town or city street address of well if located within city?
 Approximately 1 3/4 miles north and 1 1/2 miles west of Fellsburg

2 WATER WELL OWNER: Darrell N. & Natalie D. Wood Revocable Trusts/Norman & Betty Wood Revocable Trusts
 RR#, St. Address, Box # : Route 1 - Box 120
 City, State, ZIP Code : Lewis, KS 67552
 Board of Agriculture, Division of Water Resources
 Application Number: 37,002

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

4 DEPTH OF COMPLETED WELL 188 ft. ELEVATION: unknown

Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. ft.

WELL'S STATIC WATER LEVEL 28 ft. below land surface measured on mo/day/yr 1-29-03

Pump test data: Well water was Not checked ft. after hours pumping gpm

Est. Yield unknown gpm: Well water was ft. after hours pumping gpm

Bore Hole Diameter 24 in. to 188 ft., and in. to ft.

WELL WATER TO BE USED AS: 5 Public water supply 8 Air conditioning 11 Injection well
 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below)
 (2) Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well

Was a chemical/bacteriological sample submitted to Department? Yes No If yes, mo/day/yrs sample was submitted
 Water Well Disinfected? Yes No

5 TYPE OF BLANK CASING USED:

(1) Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued Clamped
 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded
 7 Fiberglass Threaded

Blank casing diameter 16 in. to 101 ft., Dia 16 in. to 139 ft., Dia 16 in. to 171 ft.
 Casing height above land surface 12 in., weight 36.87 lbs./ft. Wall thickness or gauge No .219

TYPE OF SCREEN OR PERFORATION MATERIAL:

(1) Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement
 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify)
 12 None used (open hole)

SCREEN OR PERFORATION OPENINGS ARE:

1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole)
 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes
 7 Torch cut 10 Other (specify) Bridge Slot ft.

SCREEN-PERFORATED INTERVALS: From 101 ft. to 133 ft., From 139 ft. to 151 ft.
 From 171 ft. to 187 ft., From ft. to ft.
 GRAVEL PACK INTERVALS: From 22 ft. to 188 ft., From ft. to ft.
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL: 1 Neat cement (2) Cement grout 3 Bentonite 4 Other

Grout intervals: From 0 ft. to 22 ft., From ft. to ft., From ft. to ft.

What is the nearest source of possible contamination:

1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well
 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well
 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)
 13 Insecticide storage None known

Direction from well? How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	3	Topsoil			
3	15	Clay, brown			
15	21	Clay, gray			
21	63	Sand and gravel, fine, medium, coarse			
63	98	Clay, white and brown			
98	129	Sand and gravel, fine, medium			
129	136	Clay, brown and white			
136	148	Sand and gravel, fine, medium			
148	172	Clay, white with sand, fine			
172	184	Sand and gravel, fine, medium, broken sandstone			
184	185	Clay			
185	186	Dakota Drift			
186	188	Clay			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) 1-29-03 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 2-3-03 under the business name of Clarke Well & Equipment, Inc. by (signature) *Clarke Well & Equipment, Inc.*

INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.