

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number  
 COUNTY: 024 EDWARDS SW 1/4 SW 1/4 SW 1/4 2 T 25 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?  
 2 1/2 S. 1/2 W. OF LEWIS, KANS.

2 WATER WELL OWNER: MCLEAN, ROBERT 044 Board of Agriculture, Division of Water Resources  
 RR#, St. Address, Box # : Application Number:  
 City, State, ZIP code : LEWIS, KS 67552-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 80 ELEVATION:  
 Depth(s) Groundwater Encountered 1. 36 ft. 2. ft. 3. ft.  
 WELL'S STATIC WATER LEVEL 36 ft. below land surface measured on mo/day/yr 10/24/90  
 Pump test data: Well water was ft. after hours pumping gpm  
 Estimated Yield 25 gpm: Well water was ft. after hours pumping gpm  
 Bore Hole Diameter 8.75 in. to 80 ft., and in. to ft.  
 WELL WATER TO BE USED AS: 01 DOMESTIC  
 Was a chemical/bacteriological sample submitted to department? No ;  
 If yes, mo/day/yr sample was submitted Water well disinfected? Yes

/ \					
1	---	NW	---	NE	---
M					
i	W				E
l					
e		SW		SE	
\ /					
	X				

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED  
 Blank casing diameter 5 in. to 60 ft., Dia in. to ft., Dia in. to ft.  
 Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26  
 TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC  
 SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 60 ft. to 80 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.  
 GRAVEL PACK INTERVALS: From 25 ft. to 80 ft., From ft. to ft.  
 From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE  
 Grout Intervals: From ft. to 25 ft., From ft. to ft., From ft. to ft.  
 What is the nearest source of possible contamination: CATTLE PASTURE  
 Direction from well? ALL How many feet?

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	6	SILT & SAND			
6	14	BROWN CLAY			
14	22	TAN CLAY			
22	63	05 SAND AND 17 GRAVEL			
63	65	TAN CLAY			
65	80	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 10/24/90 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 06/29/91 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse