

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: 024 EDWARDS SE 1/4 NE 1/4 SE 1/4 21 T 25 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?
4 1/2 S, 2 W. OF LEWIS, KS

2 WATER WELL OWNER: JIM MCCLAREN 177 Board of Agriculture, Division of Water Resources
RR#, St. Address, Box # : Application Number:
City, State, ZIP code : LEWIS, KS 67552-

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX: 4 DEPTH OF COMPLETED WELL 110 ELEVATION:
AN "X" IN SECTION BOX: Depth(s) Groundwater Encountered 1. 39 ft. 2. ft. 3. ft.
WELL'S STATIC WATER LEVEL 39 ft. below land surface measured on mo/day/yr
Pump test data: Well water was ft. after hours pumping gpm
Estimated Yield gpm: Well water was ft. after hours pumping gpm
Bore Hole Diameter 8.75 in. to 110 ft., and in. to ft.
WELL WATER TO BE USED AS: 01 DOMESTIC
Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: 02 PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 90 ft., Dia in. to ft., Dia in. to ft.
Casing height above land surface 12 in., weight lbs/ft. Wall thickness or gauge No. 26
TYPE OF SCREEN OR PERFORATION MATERIAL: 07 PVC
SCREEN OR PERFORATION OPENINGS ARE: 08 SAW CUT

SCREEN PERFORATED INTERVALS: From 90 ft. to 110 ft., From ft. to ft.
From ft. to ft., From ft. to ft.
GRAVEL PACK INTERVALS: From 25 ft. to 110 ft., From ft. to ft.
From ft. to ft., From ft. to ft.

6 GROUT MATERIAL 03 BENTONITE
Grout Intervals: From 1 ft. to 25 ft., From ft. to ft., From ft. to ft.
What is the nearest source of possible contamination: CATTLE PASTURE
Direction from well? ALL How many feet? 3

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
	3	SILT & SAND			
3	23	TAN CLAY			
23	58	05 SAND AND 17 GRAVEL			
58	68	TAN CLAY			
68	78	05 SAND AND 17 GRAVEL			
78	90	TAN CLAY			
90	110	05 SAND AND 17 GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 11/14/92 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 224 This Water Well Record was completed on (mo/day/yr) 11/30/92 under the business name of CARL HAYSE WATER WELL SVC by (signature) Carl Hayse