

WATER WELL RECORD Form WWC-5 KSA 82a-1212

1 LOCATION OF WATER WELL: Fraction Section Number Township Number Range Number
COUNTY: EDWARDS SW 1/4 NE 1/4 NW 1/4 32 T 25 S R 18 W

Distance and direction from nearest town or city street address of well if located within city?
4 MILES EAST, 6 MILES SOUTH OF KINSLEY

2 WATER WELL OWNER: PLATTS, PATRICK
RR#, St. Address, Box #: 607 E 7TH Board of Agriculture, Division of Water Resources
City, State, ZIP code: KINSLEY, KS 67547- Application Number:

3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:

1	NE	SE
2	NW	SW
3	NE	SE
4	NW	SW

4 DEPTH OF COMPLETED WELL 100ELEVATION: 0
Depth(s) Groundwater Encountered 1. 0 ft. 2. 0 ft. 3. 0 ft.

WELL'S STATIC WATER LEVEL 42 ft. below land surface measured on mo/day/yr 03/26/05
Pump testdata: Well water was 0 ft. after 0 hours pumping 0 gpm

Estimated Yield 0 gpm: Well water was 0 ft. after 0 hours pumping 0 gpm

Bore Hole Diameter 8.75 in. to 100 ft., and in. to 0 ft.

WELL WATER TO BE USED AS: LIVESTOCK

Was a chemical/bacteriological sample submitted to department? No ;
If yes, mo/day/yr sample was submitted Water well disinfected? Yes

5 TYPE OF BLANK CASING USED: PVC CASING JOINTS: GLUED
Blank casing diameter 5 in. to 90 ft., Dia in. to 0 ft., Dia in. to 0 ft.
Casing height above land surface 24 in., weight 0 lbs/ft. Wall thickness or gauge No. 26
TYPE OF SCREEN OR PERFORATION MATERIAL: PVC
SCREEN OR PERFORATION OPENINGS ARE: SAW CUT

SCREEN PERFORATED INTERVALS: From 90 ft. to 100 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.
GRAVEL PACK INTERVALS: From 25 ft. to 100 ft., From 0 ft. to 0 ft.
From 0 ft. to 0 ft., From 0 ft. to 0 ft.

6 GROUT MATERIAL BENTONITE
Grout Intervals: From 0 ft. to 25 ft., From 0 ft. to 0 ft., From 0 ft. to 0 ft.
What is the nearest source of possible contamination: FERTILIZER STO How many feet? 7000
Direction from well? EAST

FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	24	TAN CLAY			
24	31	SAND			
31	48	SAND AND GRAVEL			
48	58	TAN CLAY			
58	71	SAND AND GRAVEL			
71	82	TAN CLAY			
82	100	SAND AND GRAVEL			

7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was Constructed under my jurisdiction and was completed on (mo/day/year) 03/26/05 and this record is true to the best of my knowledge and belief. Kansas
Water Well Contractor's License No. 653 This Water Well Record was completed on (mo/day/yr) 04/01/05
under the business name of DAN HAYSE WATER WELL SERV by (signature) Dan Hayse