

1 LOCATION OF WATER WELL:		Fraction	Section Number	Township Number	Range Number
County: <u>Edwards</u>		$\frac{1}{4}$ N/C $\frac{1}{4}$ NW $\frac{1}{4}$	<u>36</u>	T <u>25</u> S	R <u>18</u> E/W
Distance and direction from nearest town or city street address of well if located within city? <u>1 $\frac{1}{4}$ north, $\frac{1}{4}$ east of Center View, Ks.</u>					
2 WATER WELL OWNER: <u>Bill Britton</u>					
RR#, St. Address, Box # : <u>PO Box 231</u>			Board of Agriculture, Division of Water Resources		
City, State, ZIP Code : <u>Lewis, Ks. 67552</u>			Application Number: <u>1829</u>		
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL <u>78</u> ft. ELEVATION:			
		Depth(s) Groundwater Encountered 1. _____ ft. 2. _____ ft. 3. _____ ft.			
		WELL'S STATIC WATER LEVEL <u>30 $\frac{1}{2}$</u> ft. below land surface measured on mo/day/yr <u>1-12-98</u>			
		Pump test data: Well water was _____ ft. after _____ hours pumping _____ gpm			
		Est. Yield <u>725</u> gpm: Well water was <u>54</u> ft. after <u>3</u> hours pumping <u>600</u> gpm			
		Bore Hole Diameter <u>29</u> in. to <u>78</u> ft. and _____ in. to _____ ft.			
		WELL WATER TO BE USED AS:			
		5 Public water supply 8 Air conditioning 11 Injection well			
		1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (Specify below)			
		2 <u>Irrigation</u> 4 Industrial 7 Lawn and garden only 10 Monitoring well			
		Was a chemical/bacteriological sample submitted to Department? Yes _____ No <u>X</u> ; If yes, mo/day/yr sample was submitted _____			
5 TYPE OF BLANK CASING USED:		CASING JOINTS: Glued <u>X</u> Clamped _____			
1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile		Welded _____			
2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below)		Threaded _____			
Blank casing diameter <u>16</u> in. to <u>58</u> ft. Dia _____ in. to _____ ft. Dia _____ in. to _____ ft.					
Casing height above land surface <u>12</u> in. weight _____ SDR <u>32.5</u> lbs./ft. Wall thickness or gauge No. _____					
TYPE OF SCREEN OR PERFORATION MATERIAL:		7 PVC 10 Asbestos-cement			
1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 11 Other (specify) _____					
2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 12 None used (open hole)					
SCREEN OR PERFORATION OPENINGS ARE:		8 Saw cut 11 None (open hole)			
1 <u>Continuous slot</u> 3 Mill slot 5 Gauzed wrapped 6 Wire wrapped 9 Drilled holes					
2 Louvered shutter 4 Key punched 7 Torch cut 10 Other (specify) _____					
SCREEN-PERFORATED INTERVALS: From <u>58</u> ft. to <u>78</u> ft. From _____ ft. to _____ ft.					
GRAVEL PACK INTERVALS: From <u>78</u> ft. to <u>20</u> ft. From _____ ft. to _____ ft.					
6 GROUT MATERIAL: 1 Neat cement 2 <u>Cement grout</u> 3 Bentonite 4 Other _____					
Grout Intervals: From <u>20</u> ft. to <u>0</u> ft. From _____ ft. to _____ ft.					
What is the nearest source of possible contamination:					
1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well					
2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well					
3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below)					
Direction from well? <u>west</u>		How many feet? <u>400</u>			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS
0	2	Sandy top soil			
2	9	Tough gray clay			
9	18	Brown clay			
18	21	Gray clay			
21	27	Dirty sand and gravel			
27	30	Brown clay			
30	78	Sand and gravel clean, coarse, loose			
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed, (2) reconstructed, or (3) plugged under my jurisdiction and was completed on (mo/day/year) <u>2-5-98</u> and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. <u>134</u> This Water Well Record was completed on (mo/day/yr) <u>2-10-98</u> under the business name of <u>Rosencrantz-Bemis</u> by (signature) <u>Fredia Hedson</u>					