

1 LOCATION OF WATER WELL:		Fraction		Section Number		Township Number		Range Number																																																																															
County: Sedgwick		NW 1/4 NE 1/4 NW 1/4		25		T 25 S		R 2 E (W)																																																																															
Distance and direction from nearest town or city street address of well if located within city? Approximately 2 miles south and 1 1/4 miles east of Bentley																																																																																							
2 WATER WELL OWNER: City of Wichita RR#, St. Address, Box # : 455 N. Main City, State, ZIP Code : Wichita, KS 67202 Board of Agriculture, Division of Water Resources Application Number:																																																																																							
3 LOCATE WELL'S LOCATION WITH AN "X" IN SECTION BOX:		4 DEPTH OF COMPLETED WELL 115 ft. ELEVATION: unknown																																																																																					
		Depth(s) Groundwater Encountered 1 ft. 2 ft. 3 ft. WELL'S STATIC WATER LEVEL not checked ft. below land surface measured on mo/day/yr Pump test data: Well water was not checked ft. after hours pumping gpm Est. Yield unknown gpm: Well water was ft. after hours pumping gpm Bore Hole Diameter 6 in. to 190 ft., and in. to ft. WELL WATER TO BE USED AS: 1 Domestic 3 Feedlot 6 Oil field water supply 9 Dewatering 12 Other (specify below) 2 Irrigation 4 Industrial 7 Domestic (lawn & garden) 10 Monitoring well Index Well Was a chemical/bacteriological sample submitted to Department? Yes No ☒ If yes, mo/day/yr sample was submitted Water Well Disinfected? Yes No ☒																																																																																					
		5 TYPE OF BLANK CASING USED:																																																																																					
		1 Steel 3 RMP (SR) 5 Wrought iron 8 Concrete tile CASING JOINTS: Glued ☒ Clamped 2 PVC 4 ABS 6 Asbestos-Cement 9 Other (specify below) Welded 7 Fiberglass Threaded Blank casing diameter 2 in. to 93 ft., Dia in. to ft., Dia in. to ft. Casing height above land surface 24 in., weight .96 lbs./ft. Wall thickness or gauge No .218																																																																																					
		TYPE OF SCREEN OR PERFORATION MATERIAL: 1 Steel 3 Stainless steel 5 Fiberglass 8 RMP (SR) 10 Asbestos-cement 2 Brass 4 Galvanized steel 6 Concrete tile 9 ABS 11 Other (specify) 12 None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: 1 Continuous slot 3 Mill slot 5 Gauzed wrapped 8 Saw cut 11 None (open hole) 2 Louvered shutter 4 Key punched 6 Wire wrapped 9 Drilled holes 7 Torch cut 10 Other (specify) ft.																																																																																					
		SCREEN-PERFORATED INTERVALS: From 93 ft. to 113 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 68 ft. to 123 ft., From ft. to ft. From ft. to ft., From ft. to ft.																																																																																					
6 GROUT MATERIAL: 1 Neat cement 2 Cement grout 3 Bentonite 4 Other Bentonite Holeplug Grout Intervals: From 0 ft. to 61 ft., From 129 ft. to 190 ft., From 61 - 68 ft. to 123 - 129 ft. What is the nearest source of possible contamination: 1 Septic tank 4 Lateral lines 7 Pit privy 10 Livestock pens 14 Abandoned water well 2 Sewer lines 5 Cess pool 8 Sewage lagoon 11 Fuel storage 15 Oil well/Gas well 3 Watertight sewer lines 6 Seepage pit 9 Feedyard 12 Fertilizer storage 16 Other (specify below) 13 Insecticide storage None known Direction from well? How many feet?																																																																																							
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr><td>0</td><td>4</td><td>Topsoil</td><td></td><td></td><td></td></tr> <tr><td>4</td><td>31</td><td>Sand and gravel, coarse, medium, fine, very loose, clean</td><td></td><td></td><td></td></tr> <tr><td>31</td><td>40</td><td>Clay, tan and dark gray</td><td></td><td></td><td></td></tr> <tr><td>40</td><td>51</td><td>Sand and gravel, medium, fine</td><td></td><td></td><td></td></tr> <tr><td>51</td><td>60</td><td>Clay, white</td><td></td><td></td><td></td></tr> <tr><td>60</td><td>66</td><td>Clay, white, sandy, soft</td><td></td><td></td><td></td></tr> <tr><td>66</td><td>75</td><td>Clay, green</td><td></td><td></td><td></td></tr> <tr><td>75</td><td>83</td><td>Clay, dark gray and green</td><td></td><td></td><td></td></tr> <tr><td>83</td><td>126</td><td>Sand, medium, fine, very fine</td><td></td><td></td><td></td></tr> <tr><td>126</td><td>129</td><td>Clay, gray</td><td></td><td></td><td></td></tr> <tr><td>129</td><td>186</td><td>Sand, medium, fine, very fine</td><td></td><td></td><td></td></tr> <tr><td>186</td><td>190</td><td>Shale, black</td><td></td><td></td><td></td></tr> </tbody> </table>										FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS	0	4	Topsoil				4	31	Sand and gravel, coarse, medium, fine, very loose, clean				31	40	Clay, tan and dark gray				40	51	Sand and gravel, medium, fine				51	60	Clay, white				60	66	Clay, white, sandy, soft				66	75	Clay, green				75	83	Clay, dark gray and green				83	126	Sand, medium, fine, very fine				126	129	Clay, gray				129	186	Sand, medium, fine, very fine				186	190	Shale, black			
FROM	TO	LITHOLOGIC LOG	FROM	TO	PLUGGING INTERVALS																																																																																		
0	4	Topsoil																																																																																					
4	31	Sand and gravel, coarse, medium, fine, very loose, clean																																																																																					
31	40	Clay, tan and dark gray																																																																																					
40	51	Sand and gravel, medium, fine																																																																																					
51	60	Clay, white																																																																																					
60	66	Clay, white, sandy, soft																																																																																					
66	75	Clay, green																																																																																					
75	83	Clay, dark gray and green																																																																																					
83	126	Sand, medium, fine, very fine																																																																																					
126	129	Clay, gray																																																																																					
129	186	Sand, medium, fine, very fine																																																																																					
186	190	Shale, black																																																																																					
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was (1) constructed (2) reconstructed or (3) plugged under my jurisdiction and was completed on (mo/day/year) 11-6-01 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No 185 This Water Well Record was completed on (mo/day/yr) 11-13-01 under the business name of Clarke Well & Equipment, Inc. by (signature) <i>Clarke Well & Equipment, Inc.</i>																																																																																							
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks, underline or circle the correct answers. Send top three copies to Kansas Department of Health and Environment, Bureau of Water, Topeka, Kansas 66620-0001. Telephone 785-296-5524. Send one to WATER WELL OWNER and retain one for your records. Fee of \$5.00 for each constructed well.																																																																																							