


WATER WELL RECORD

Form WWC-5

Division of Water Resources App. No.

40518

1 LOCATION OF WATER WELL: County: Sedgwick		Fraction SE ¼ NW ¼ SW ¼ ¼		Section Number 22	Township No. T 25 S	Range Number R 2 ☐ E ☒ W																																																																		
Street/Rural Address of Well Location; if unknown, distance & direction from nearest town or intersection: If at owner's address, check here ☐ From Bently, KS: 2 miles South and 3/4 of a mile West.				Global Positioning System (GPS) information: Latitude: (in decimal degrees) Longitude: (in decimal degrees) Elevation: Datum: ☐ WGS 84, ☐ NAD 83, ☐ NAD 27 Collection Method: ☐ GPS unit (Make/Model:) ☐ Digital Map/Photo, ☐ Topographic Map, ☐ Land Survey Est. Accuracy: ☐ <3 m, ☐ 3-5 m, ☐ 5-15 m, ☐ >15 m																																																																				
2 WATER WELL OWNER: Richard Basore RR#, Street Address, Box #: 15531 W 93rd St. N. City, State, ZIP Code : Sedgwick, KS 67135																																																																								
3 LOCATE WELL WITH AN "X" IN SECTION BOX: N  W E S [-----1 mile-----]		4 DEPTH OF COMPLETED WELL 220 ft. Depth(s) Groundwater Encountered (1) 22 ft. (2) ft. (3) ft. WELL'S STATIC WATER LEVEL 22 ft. below land surface measured on mo/day/yr. 6/15/09 Pump test data: Well water was ft. after hours pumping gpm EST. YIELD 800 gpm. Well water was ft. after hours pumping gpm Bore Hole Diameter in. to ft., and in. to ft. WELL WATER TO BE USED AS: ☐ Public water supply ☐ Geothermal ☐ Injection well ☐ Domestic ☐ Feedlot ☐ Oil field water supply ☐ Dewatering ☐ Other (Specify below) ☒ Irrigation ☐ Industrial ☐ Domestic-lawn & garden ☐ Monitoring well Was a chemical/bacteriological sample submitted to Department? ☐ Yes ☒ No If yes, mo/day/yr sample was submitted Water well disinfected? ☒ Yes ☐ No																																																																						
5 TYPE OF CASING USED: ☐ Steel ☒ PVC ☐ Other CASING JOINTS: ☒ Glued ☐ Clamped ☐ Welded ☐ Threaded Casing diameter 16 in. to 180 ft., Diameter in. to ft., Diameter in. to ft. Casing height above land surface 12 in., Weight 18 lbs./ft., Wall thickness or gauge No. SDR 26 TYPE OF SCREEN OR PERFORATION MATERIAL: ☐ Steel ☐ Stainless Steel ☒ PVC ☐ Other (Specify) ☐ Brass ☐ Galvanized Steel ☐ None used (open hole) SCREEN OR PERFORATION OPENINGS ARE: ☐ Continuous slot ☐ Mill slot ☐ Gauze wrapped ☐ Torch cut ☐ Drilled holes ☐ None (open hole) ☐ Louvered shutter ☐ Key punched ☐ Wire wrapped ☒ Saw cut ☐ Other (specify) SCREEN-PERFORATED INTERVALS: From 180 ft. to 220 ft., From ft. to ft. From ft. to ft., From ft. to ft. GRAVEL PACK INTERVALS: From 20 ft. to 55 ft., From ft. to ft. From 170 ft. to 220 ft., From ft. to ft.																																																																								
6 GROUT MATERIAL: ☐ Neat cement ☐ Cement grout ☒ Bentonite ☐ Other Grout Intervals: From 3 ft. to 20 ft., From 55 ft. to 75 ft., From 160 ft. to 170 ft. What is the nearest source of possible contamination: ☐ Septic tank ☐ Lateral lines ☐ Pit privy ☐ Livestock pens ☐ Insecticide storage ☐ Other (specify below) ☐ Sewer lines ☐ Cesspool ☐ Sewage lagoon ☐ Fuel storage ☒ Abandoned water well ☐ Watertight sewer lines ☐ Seepage pit ☐ Feedyard ☐ Fertilizer storage ☐ Oil well/gas well Direction from well East Distance from well 55'																																																																								
<table border="1" style="width:100%; border-collapse: collapse;"> <thead> <tr> <th>FROM</th> <th>TO</th> <th>LITHOLOGIC LOG</th> <th>FROM</th> <th>TO</th> <th>LITHO. LOG (cont.) or PLUGGING INTERVALS</th> </tr> </thead> <tbody> <tr> <td>0</td> <td>5</td> <td>top soil</td> <td>192</td> <td>193</td> <td>clay</td> </tr> <tr> <td>5</td> <td>50</td> <td>gravel</td> <td>193</td> <td>203</td> <td>fine sand</td> </tr> <tr> <td>50</td> <td>75</td> <td>clay</td> <td>203</td> <td>205</td> <td>clay</td> </tr> <tr> <td>75</td> <td>106</td> <td>very fine sand</td> <td>205</td> <td>212</td> <td>fine to medium sand</td> </tr> <tr> <td>106</td> <td>115</td> <td>clay</td> <td>212</td> <td>214</td> <td>clay</td> </tr> <tr> <td>115</td> <td>125</td> <td>fine sand</td> <td>214</td> <td>220</td> <td>fine to medium sand</td> </tr> <tr> <td>125</td> <td>145</td> <td>clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>145</td> <td>155</td> <td>fine sand</td> <td></td> <td></td> <td></td> </tr> <tr> <td>155</td> <td>188</td> <td>tan clay</td> <td></td> <td></td> <td></td> </tr> <tr> <td>188</td> <td>192</td> <td>fine sand</td> <td></td> <td></td> <td></td> </tr> </tbody> </table>							FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS	0	5	top soil	192	193	clay	5	50	gravel	193	203	fine sand	50	75	clay	203	205	clay	75	106	very fine sand	205	212	fine to medium sand	106	115	clay	212	214	clay	115	125	fine sand	214	220	fine to medium sand	125	145	clay				145	155	fine sand				155	188	tan clay				188	192	fine sand			
FROM	TO	LITHOLOGIC LOG	FROM	TO	LITHO. LOG (cont.) or PLUGGING INTERVALS																																																																			
0	5	top soil	192	193	clay																																																																			
5	50	gravel	193	203	fine sand																																																																			
50	75	clay	203	205	clay																																																																			
75	106	very fine sand	205	212	fine to medium sand																																																																			
106	115	clay	212	214	clay																																																																			
115	125	fine sand	214	220	fine to medium sand																																																																			
125	145	clay																																																																						
145	155	fine sand																																																																						
155	188	tan clay																																																																						
188	192	fine sand																																																																						
7 CONTRACTOR'S OR LANDOWNER'S CERTIFICATION: This water well was ☒ constructed, ☐ reconstructed, or ☐ plugged under my jurisdiction and was completed on (mo/day/year) 6/15/09 and this record is true to the best of my knowledge and belief. Kansas Water Well Contractor's License No. 238 This Water Well Record was completed on (mo/day/year) 6/15/09 under the business name of Premier Pump and Well Service, Inc. by (signature) Emma Kuchubian																																																																								
INSTRUCTIONS: Use typewriter or ball point pen. PLEASE PRESS FIRMLY and PRINT clearly. Please fill in blanks and check the correct answers. Send three copies (white, blue, pink) to Kansas Department of Health and Environment, Bureau of Water, Geology Section, 1000 SW Jackson St., Suite 420, Topeka, Kansas 66612-1367. Telephone 785-296-5522. Send one copy to WATER WELL OWNER and retain one for your records. Include fee of \$5.00 for each constructed well. Visit us at http://www.kdheks.gov/waterwell/index.html .																																																																								