

Form WWC-5

Division of Water Resources App. No.

[illegible]

Sargent Irrigation

WELL AND PUMP SERVICE

PO Box 268
Holdrege, NE 68949

825 Brewster Road

Phone: (308) 995-6143
1-800-860-2946

TEST HOLE LOG

CUSTOMER: Wichita, KS	
WELL ID: OB55D	
LOCATION: SE ¼ SE ¼ SW ¼ SE ¼, 5-T25S-R2W, Sedgwick Co., KS	
LATITUDE: 37° 53' 53.8"	
LONGITUDE: -97° 33' 37.1"	
FOOTAGES: 205' from the South section line and 1413 feet from the East section line.	
DATE: 10/26/09	DRILLED BY: Kyle Schoff, Doug Rezac, Cody Hanson

SWL:

PWL:

GPM:

from feet - to feet

0	5	Top soil and soft sandy clay
5	10	Sandy clay and fine to medium gravel
10	15	Fine to medium gravel with thin sandy clay strips
15	20	Fine to medium gravel
20	25	Coarse sand to medium gravel
25	30	Coarse sand to medium gravel with traces of gray clay
30	35	Coarse sand to medium gravel with traces of gray sand clay
35	40	Coarse to medium gravel with traces of sandy clay
40	50	Coarse sand to medium gravel
50	55	Coarse sand to medium gravel with traces sandy clay
55	60	Coarse to medium gravel with thin sandy clay layers
60	70	Coarse sand to medium gravel and sandy clay
70	80	Sandy clay

Well Information:

Well depth: 67'
Plain casing: 47'
Perf. Set: 47'-67'

Bore hole: 6
Perf. casing: 20'
Gravel: 42-67'

Casing size: 2"
Slot size: .020"
Grout: 0-42'